


# PUBLIC LAND CORNERS

WEYERHAEUSER COMPANY  
 SPRINGFIELD BRANCH



TOWNSHIP 25S RANGE 2W  
 SECTION 28 CORNER W $\frac{1}{4}$   
 COUNTY Douglas OREGON

**GLO SURVEY RECORD**

PRESENT CONDITION - (DESCRIBE FULLY - USE PAGE 2 IF NEEDED FOR EXPLANATION.)

DATE: 1900  
 CORNER Basalt stone marked  $\frac{1}{4}$  on west side

Found

ACCESSORIES:

	BEARING-	LINKS-	FEET-	
12" Hemlock	N41°E	31	20.5	20" Hemlock stump, face beaded over
20" Fir	S81°W	59	38.9	20" Fir snag - scribing visible

GLO SURVEY RECORD

PRESENT CONDITION:

DATE: 1962  
 Found original stone and both original BTs -  
 Set brass cap and placed original stone  
 alongside in mound of stone and marked:  
 "BXO" on rock outcrop under overhang  
 S70 $\frac{1}{2}$ °E 36 $\frac{1}{2}$  Lks. 24.1'  
 10" Cedar N68 $\frac{1}{2}$ °W 42 $\frac{1}{2}$  Lks. 28.0'

Found brass cap  
 Found "BXO" chiseled into rock as  
 described  
 10" Cedar - scribing visible

CORNER SET: Brass cap in place as set by 1962  
Cadastral renewal

MAG. DECL.:

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-	SURVEY -	
N39°E	20.5	1900	Distance to face
S84°W	38.9	1900	Distance to face
S71°E	25.1	1962	Distance to "X" on rock face
N67°W	28.8	1962	Distance to face



ACCESSORIES ADDED THIS DATE:

MAGNETIC DECLINATION

20°

	BEARING	FEET	ORIG. B.T.	"W" NAIL	PLATE	BRASS DISC
60" Fir	S19°W	9.6	-	X	X	-
26" Hemlock stump	N39°E	19.8	GLO 1900	X	X	-

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: rocky slope

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) \_\_\_\_\_ ON MINUS (-) \_\_\_\_\_ %

NORTH: - 50%

SOUTH: + 72%

EAST: + 82% 25' to rock outcrop and overhang.

WEST: - 33%

FROM CORNER -

WORK DONE FOR W. CO. \_\_\_\_\_

FIELD NOTES IN BOOK: \_\_\_\_\_

BY: Glen McChesney DATE: 12/30/69

~~ENGINEER SUPERVISOR~~  
Project Engineer

ASSISTED BY: Leon Warren

UNDER THE SUPERVISION OF:

COPIES SENT TO: \_\_\_\_\_

SEAL

PAGE 3

C. S. File No. \_\_\_\_\_