


PUBLIC LAND CORNERS.

WEYERHAEUSER COMPANY
SPRINGFIELD BRANCH



TOWNSHIP 26S RANGE 2W
SECTION 6 CORNER S $\frac{1}{2}$
COUNTY Douglas OREGON

GLO SURVEY RECORD

DATE: 1959

CORNER Brass Cap

PRESENT CONDITION - (DESCRIBE FULLY -
USE PAGE 2 IF NEEDED FOR EXPLANATION.)

Found in good shape

ACCESSORIES:

	BEARING-	LINKS-	FEET-	
<u>28" Fir</u>	<u>S11°E</u>		<u>21.1</u>	<u>BT face pitched over</u>
<u>29" Fir</u>	<u>N57$\frac{1}{2}$°W</u>		<u>21.1</u>	<u>BT scribing visable.</u>

SURVEY RECORD

DATE: _____

PRESENT CONDITION: _____

CORNER SET: _____

MAG. DECL.: _____

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-	SURVEY -	

C553/114-1

ACCESSORIES ADDED THIS DATE: 7/14/66

MAGNETIC DECLINATION 20° E

	BEARING	FEET	ORIG. B. T.	"W" NAIL	PLATE	BRASS DISC
24" Fir	N51°E	12.3		x	x	
40" Fir	S35°W	12.7		x	x	

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: Salal, Hazel, Sword fern, Ocean spray, old growth stand.

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) S5°E ON MINUS (-) 16 %

FROM CORNER |

NORTH: + 40 %

SOUTH: - 16 %

EAST: - 7 %

WEST: + 11 % 130' to Spur

WORK DONE FOR W. CO.

FIELD NOTES IN BOOK:

BY: J.E. Shaw DATE: 7/14/66
ENGINEER - SURVEYOR

ASSISTED BY: H.E. Case

COPIES SENT TO:

UNDER THE SUPERVISION OF:

SEAL