


PUBLIC LAND CORNERS

13

15

WEYERHAEUSER COMPANY
SPRINGFIELD BRANCH



TOWNSHIP 26 South RANGE 3 West

SECTION 24 CORNER NE

COUNTY Douglas OREGON

GLO SURVEY RECORD

DATE: 1885
CORNER Post

PRESENT CONDITION - (DESCRIBE FULLY - USE PAGE 2 IF NEEDED FOR EXPLANATION.)

No trace

ACCESSORIES:

| | BEARING- | LINKS- | FEET- |
|-------------|----------|--------|-------|
| 15" Laurel | S 05 W | 190 | 125.4 |
| 12" Laurel | S 17 E | 140 | 92.4 |
| 5" Red Fir | N 88 W | 10 | 6.6 |
| 12" Red Fir | N 85 E | 20 | 13.2 |
| | | | |
| | | | |
| | | | |

No trace
No trace
No trace
No trace

Re- **SURVEY RECORD**

DATE: 1910
Re-established by Deputy Gibbs. He found post but all Bts were destroyed

PRESENT CONDITION:

Set Granite stone 7 x 11 x 15

| | | | |
|------------|--------|----------|-------|
| 24" Fir | N 53 E | 108 lks. | 71.3 |
| 24" Fir | S 80 E | 31 lks. | 20.5 |
| 12" Laurel | S 05 W | 190 lks. | 125.4 |
| 17" Fir | N 15 W | 12 lks. | 7.9 |


Found notches on north and south edges
Found 28" fir - opened face - scribing visible
Not found
Fir slab 5" high - scribing visible

CORNER SET: stone as found MAG. DECL.: 20

Se page 2 for Douglas County renewal

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

| BEARING- | FEET- | SURVEY - |
|----------|-------|----------|
| N 53 E | 78.8 | 1910 |
| S 84 E | 26.4 | 1910 |
| N 15 W | 7.9 | 1910 |
| | | |
| | | |
| | | |



--- LINE MARKED BY NOTCH CUT IN BLAZE.

○---KNOWN CORNER.

⊗---REFERENCED CORNER BY WEYERHAEUSER METHOD.

Len. #114

6/4/65 - Douglas County survey crew renewed this corner today by putting in Brass cap at position of stone and setting stone alongside and scribing two new Bts as follows:

| | | | | |
|--------|--------|-------|---------|----------------------------|
| 6" Fir | N 74 W | 25.4' | scribed | T 26 S R 3 W Section 13 Bt |
| 6" Fir | S 87 W | 13.1' | scribed | T 26 S R 3 W Section 24 Bt |

Douglas County Survey Crew: Ray Tracy
 Mike Darby
 Terry Connell
 Present - Glen McChesney

ACCESSORIES ADDED THIS DATE:

MAGNETIC DECLINATION 20

| | BEARING | FEET | ORIG. B.T. | "W" NAIL | PLATE | BRASS DISC |
|------------|---------|------|------------|----------|-------|------------|
| 28" Fir | N 54 E | 77.6 | X | X | X | - |
| 6" Hemlock | N 24 E | 13.0 | - | X | X | - |
| 6" Fir | S 86 W | 13.1 | - | X | X | -- |
| 9" Fir | S 25 W | 19.0 | | | | |

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: _____

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) N 25 E ON MINUS (-) 93 %

Old burn - residual old growth, snags, and Fir reproduction

FROM CORNER |

NORTH: - 85%

SOUTH: 72%

EAST: 11%

WEST: - 10%

WORK DONE FOR W. CO. _____

FIELD NOTES IN BOOK: _____

BY: Allen McCasney DATE: 5/28/65

ENGINEER SURVEYOR
LAND AGENT

ASSISTED BY: Eldon Case

UNDER THE SUPERVISION OF:

FILED
RECEIVED

OCT 19 1965

COPIES SENT TO: _____

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE

SEAL

PAGE 3

S. File No. 53/115