

Renew  $\frac{1}{4}$   $\frac{527}{534}$  T255 R3W

Fd. G.L.O. BRASS CAP MKD. " $\frac{1}{4}$   $\frac{527}{534}$  1943"

#1943 RESURVEY BT'S AS FOLLOWS -

40" NOW 40" FIR N.  $7^{\circ}$  E. 28  $\frac{1}{4}$  FT.

SHOWS " $\frac{1}{4}$  527 BT" ON UNHEALED BLAZE - NOW DEAD SNAG.

48" NOW 50" FIR S.  $64^{\circ}$  E. 10  $\frac{1}{2}$  FT.

SHOWS GOOD SCAR - WE DO NOT OPEN - ALIVE.

WE MARK NEW BT'S -

9" Hemlock N.  $51^{\circ}$  E. 26  $\frac{1}{4}$  FT.

MKD " $\frac{1}{4}$  527 CS BT"

7" Hemlock S.  $29^{\circ}$  E. 9  $\frac{1}{2}$  FT.

MKD. " $\frac{1}{4}$  534 CS BT"

THIS COR LIES 2+ S.E. COR. OF


CUTOFF UNIT IN SEC. 27 APPROX.

1000 FT. EAST OF KELLEY CREEK RD.

June 30, 1966

V.R.T.  
J.B.  
J.H.

FILED  
RECEIVED



JUN 30 1966

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

O.K. J.W.B.

\*#56

C.S. File No. 54/27-7