

521/522

Renew Sec. Cor. 528/527 T255 R3W

Fd. G.L.O. BR255 cap MKd. T255 R3W ^{521/522} 528/527

1943 " with Steel fence post set along side.

& one Live B.T. 25 Follows -

ORIG. 1883 28" now 32" Hemlock S. 55° E, 18 1/2 ft.

with 1943 scribe " T255 R3W 527 BT " visible

on partially healed blaze. - N.E. & N.W.

B.T.'s are now stamps with scribes showing.

Both B.T.'s to SW. are gone due to cat Rd.

we mk. new B.T.'s -

7" Hemlock, N. 60° E, 13 1/2 ft.

Mkd. " T255 R3W 522 CS BT "

8" Hemlock S. 28° W, 58 1/2 ft.

Mkd. " T255 R3W 528 CS BT "

5" Hemlock N. 73° W, 42 1/2 ft.

Mkd. " 521 CS BT "

This cor. Lies in old Logged unit


approx 600 ft. W. of N.-S. cutting

line.

July 12, 1966

FILED
RECEIVED
V. B.T.

JUL 12 1966



COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

468
* C.R. J.W.B.

C.S. No. 57/27-25