

54 | 53

Renew Sec. CoR. 59 | 510 T255 R3W

Fd. GLO BRASS CAP MKD. " T255 R3W

54 | 53  
59 | 510 1943" with steel fence post

set along side. & Following B.T.s. 2 live & in good cond. Also Recorded in Ren #5.

8" Now 13" D. FIR S, 58 1/2° W, 23 8/10 ft.

Shows good SCAR - we do not open.

6" Now 12" Hemlock N. 51° W, 3 3/10 ft.

Shows good SCAR - we do not open.

Maple to SE. Down & 20" FIR to S.E.

gone, Cedar stump to N.E. very badly

BURNED. & 62" FIR To N.E. Now STUMP.

WEMK. New B.T.s -

9" D. FIR N, 81° E, 18 4/10 ft.

MKD. " T255 R3W 53 CS BT"

11" D. FIR S, 18° E, 31 3/10 ft.

MKD. " T255 R3W 510 CS BT"


COR. Lies on Gentle N.E. Slope

on Bench.

August 4, 1966 FILED V.R.T.

RECEIVED

AUG 4 1966



COUNTY SURVEYOR

DOUGLAS COUNTY, ORE. 52  
C.S. File No. 54/277

\*91  
D.K. J.W.B.