

Renew  $\frac{1}{4}$  55/54 T255 R3W

Fd. G.L.O. Brass Cap MKd. " $\frac{1}{4}$  55/54

1944 "with steel fence post along  
side & stumps of B.T.s 25 follows

20" now 24" Fir (stump) S.  $28^{\circ}$  E, 12<sup>5</sup> ft.

Shows healed blaze. - Ren. #7 B.T.

40" now 40" Fir (stump) N.  $43\frac{1}{2}^{\circ}$  W. 23<sup>8</sup> ft.

Shows " $\frac{1}{4}$  55 T255 R3W CS BT" on unhealed  
blaze - Ren. #7 B.T. -

14" now 20" cedar (stamp) N.  $14\frac{1}{4}^{\circ}$  W. 33<sup>2</sup> ft.

Shows " $\frac{1}{4}$  55 BT" scribe on partially  
healed blaze - 1944 Resurvey B.T.

WEMK. New B.T.'s -

4" W. Fir S.  $14^{\circ}$  E, 28<sup>0</sup> ft.

Mkd. " $\frac{1}{4}$  54 CS BT"

6" R. cedar S.  $42^{\circ}$  W. 16<sup>3</sup> ft.

Mkd. " $\frac{1}{4}$  55 CS BT"

This cor. lies on steep S.W.

slope approx 400 ft N. of


Hinckle Creek Road

FILED

August 4, 1966

RECEIVED

V.A.T.  
AUG 7 1966  
J.N.



COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

\* #95  
O.K. J.W.B.

C.L.R. 54/27-56