

Renew Sec. Cor.  $\frac{523}{526} | \frac{524}{525}$  T245 R3W

Fd. C.B.T.s 25 follows -

orig. 48" Fir N. 35° E 28  $\frac{1}{2}$  ft.

Now shattered snag - any scribe or scar  
would be approx 5 ft. below logging debris.

orig. 40" now 44" Fir S. 40° W. 37  $\frac{1}{2}$  ft.

Now stump - shows scar - we do not open.

orig. 24" now 28" Hemlock S. 55° E. 25  $\frac{1}{2}$  ft.

Now stump - we open & find 8" scribe

& Reverse - No Trace MH C.B.T. at cor.

point - set 1" I.P. & BRASS cap MKd.

"COUNTY SURVEYORS OFFICE

1968 T245  $\frac{523}{526} | \frac{524}{525}$  R3W" & MK. new

B.T.s -

35" Fir STUMP N. 53° W. 31  $\frac{1}{2}$  ft.

MKd. "T245 R3W 523 CS BT"

46" Fir STUMP S. 52° E. 43  $\frac{1}{2}$  ft.

MKd. "T245 R3W 525 CS BT"

No Live Trees available. This

cor. lies on very steep N.E.


slope

March 18, 1968

URT

J.H.

J.P.



O.K. J.W.O.

C.S. File No.

54/27,146