

Searched For & Fd Following

59 / 510
816 / 515

T31-60

12" Yew which had been
opened for scribing 'S' visible
This tree however is out of the
ground.

All other trees not found.

Being unable to determine
where Yew stood, I could
not recover this car.

Tagged Yew & also Tagged
D. Fir in creek for approx.
location.

Best way to reach this car
is by walking about 1 1/2
miles up catching creek
on very old logging rd.

Tagged D. Fir is very easily
seen in creek.

11-3-66

John W. B.

O.K. J.W.B.

DIETZGEN NO. 385-6

Renewal ^{9/10} 16¹⁵ T31SR6W

Found: one old original B.T.
a 12" yew out of the ground
with scribed '3, visible,
also 1" BLM Iron pipe that
was agreed to be corner by
BLM and C3D Lumber Co.

Set: Brass CAP Mkd. County
Surveyors Office T31SR6W
S9 S10 | S15 S16 1970 besides
Iron pipe.

New B.T.'S: 48" D. Fir S11E 962
scribed T31SR6WS15CS BT

5" Alder N85E 105
scribed T31SR6WS10CS BT

36" D. Fir S67W 100
scribed T31SR6WS16CS BT

18" yew N14W 59E
scribed T31SR6WS9CS BT


Note: corner lies on West side
of creek. at Record Dist

SEE C3 FILE

W. Penley
J. Heritage
9-14-70

JAMES W. BYRON
COUNTY SURVEYOR

PHONE 672-3311
EXTENSION 28



COUNTY OF DOUGLAS
OFFICE OF THE SURVEYOR
ROSEBURG, OREGON

August 24, 1970

Bureau of Land Management
Mr. Dwain Davis
P. O. Box 1045
Roseburg, Oregon 97470

Dear Sir:

In regard to your letter verifying the location of the S. W. corner of Section 10, T. 31 S., R. 6 W., we would like to have the information of the corner point as established by you in August, 1969.

Enclosed is a copy of John Powell's record of this corner.

Yours truly,

James W. Byron
County Surveyor

JWB/11
Enclosure

CS 54/31-47



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

District Office

P. O. Box 1045

Roseburg, Oregon 97470

AUG 18 1970

Memorandum

To: South Area Manager

From: South Umpqua Timber Manager

Subject: Section Corner, Section 10, T. 31 S., R. 6 W.

On February 6, 1970 Mark Ashton and I met with Jim Combs of C & D Lumber Company for the purpose of verifying the location of the SW corner of Section 10, T. 31 S., R. 6 W.

The corner point was established with staff compass and chain from an original BT. This is a yew tree which has fallen down. A scribed 3 is visible and the tree was confirmed as a BT by a county surveyor on 11-3-66. The corner point was established by Dwain Davis of this office in August of 1969. After checking his work we drove a one inch pipe down through some old logs and referenced it with tags on two trees.

C & D & B LUMBER COMPANY

7" yew S16W from corner 4.5 ft.

36" fir S67W from corner 10 ft., measurements to center of trees.

The corner is on the west side of the creek.

The ownership of the lands adjoining this corner is Government and C&D Lumber Co. Mr. Bud Johnson designated Mr. Combs as his representative to check on this corner and we agree that is a satisfactory location.

I suggest we ask Mr. Johnson to sign this report indicating agreement and a copy be sent to the Cadastral Engineers.

KOELLE/erc
8-5-70

Paul Koelle
Bud Johnson

FILED
RECEIVED

AUG 20 1970

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

→ S 54/31-47