

Johnson Bros. Lumber Co.

SPECIALIZING IN PRODUCTION OF QUALITY FINISHED LUMBER FROM FIR CEDAR AND HEMLOCK

February 9, 1967

County Surveyor
Douglas County Court House
Roseburg, Oregon

Dear Sir:

On Feb. 8, 1967, I restored the 1/4 corner between Secs 19 & 30, T. 19S, R. 8W, W.M. as follows:

From G. L. O. notes dated October 2, 1891
1/4 Sec. Cor. Squared post
Cedar 18" dia. brs S70 1/2 E 50 lks
Fir 48" dia. brs N6E 35 lks


Evidence Found:

Both B.T.S. are rotted down almost to ground level. No stake could be found. No scribing visible.

Restoration Notes:

Set 1" pipe 24" long 18" into the ground for the 1/4 Sec. Cor. For reference drove a 3/8 x 8" spike into a 56" Fir stump. Spike is N 77-1/2 E 41.5' from 1/4 corner. Drove a 3/8 x 8" spike into a 40" Fir tree. Spike is S 56-1/2 E 63.9' from the 1/4 corner.

If you need any more information for your records, please contact me.




FILED
RECEIVED

SK:j

FEB 11 1967 #4

COUNTY SURVEYOR RAILWAY AND CAR MATERIALS • INDUSTRIAL CLEARS
DOUGLAS COUNTY, ORE.



C. S. File No. 55/26