


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

As surveyed by Charles L. Campbell Deputy Surveyor, under Contract No. 747, dated 1902

Original survey states: Set a basalt stone, 24x12x4 ins., for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on North face. Raise mound of stone, 3 ft. base, 2 ft. high, North of cor.




Description of corner evidence found:

A stone 24x12x4 ins. marked $\frac{1}{4}$ on North face
A mound of stone North of corner

Description of monument and accessories I established to perpetuate the original location of this corner

At the position of the stone I set a 2" by 30" galvanized iron pipe, with a brass cap, 24" in the ground and placed the stone alongside.

I stamped the disk



From the pipe monument, I marked the following trees:

- A fir, 32 ins. dia. bears N15*W 41.8 ft.
Marked $\frac{1}{4}$ S18 BT
- A fir, 28 ins. dia. bears S4*B 23.9 ft.
Marked $\frac{1}{4}$ S19 BT

REGISTERED
OREGON
LAND SURVEYOR

Glenn S. Baughman

JULY 14, 1961
GLENN S. BAUGHMAN
and facing

I placed bearing tree tags on all bearing trees the monument.

Office of Surveyor County of Douglas
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 23 day of August, 1968, at 10 o'clock A.m., (signed)
James H. Johnson by _____
(COUNTY OFFICIAL) (DEPUTY)

FILED
RECEIVED

AUG 23 1968

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

Form R6-7100-57 (9/66)
140400

File No. 55/87 -6