

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

As surveyed by Charles L. Campbell Deputy surveyor, under Contract No. 747 Dated 1902

Original survey states: Set an ironstone 28x12x12x ins. for cor. of secs. 20,21,28, and 29, marked with 2 notchs on the south and 4 notchs on the East edges, from which:

A fir, 20 ins. dia. bears N10½E., 41 lks.

Marked T32S R2W S21 BT

A fir, 36 ins. dia. bears S77½E, 34 lks.

Marked T32S R2W S28 BT

A fir, 48 ins. dia. bears S73*W, 38 lks.

Marked T32S R2W S29 BT


A fir, 28 ins. dia. bears N19 3/4*W 35 lks.

Marked T32S R2W S20 BT

Description of corner evidence found:

No stone

A fir 52 ins. dia. bears S73*W 25.2 ft. with open face, scribes are in good condition Marked T32S R2W S29 BT



Description of monument and accessories I established to perpetuate the original location of this corner

Using the record bearing and distance I set a 2" by 30" galvanized iron pipe, with brass cap, 24" in the ground.

I stamped the disk

From the pipe monument, the original bearing tree is:

A fir, 52 ins. dia. bears S73*W 25.2 ft.

I marked the following bearing trees:

A fir 6 ins. dia. bears N79*W 11.5 ft.

Marked T32S R2W S20 BT

A fir 23 ins. dia. bears N30*E 66.8 ft.

Marked T32S R2W S21 BT

No other trees within limits

I set bearing tree tags on all bearing trees and facing the monument.

Office of Surveyor..... County of Douglas

State of Oregon....., I hereby certify that the within instrument was filed in this office

FILED for record on the 23 day of August, 1968, at 10 o'clock A.m., (signed)


RECEIVED *James W. Peyton* by (DEPUTY)

AUG 23 1968

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

300300

*44 Form R6-7100-57 (9/66)



REGISTERED
OREGON
LAND SURVEYOR

Glenn S. Baughman

JULY 14, 1967
GLENN S. BAUGHMAN
536

C. S. File No. 55/87 -10