

RESTORED CORNER FOR STATE OF OREGON--DEPARTMENT OF FORESTRY

Section corner common to Sections 23 and 26 (East end), T22S, R12W, W.M., Douglas County, Oregon.

ORIGINAL

Post and bearing trees missing

Creek, 20 links wide, course N20W, bears S89° 48' West 1.75 chains; in place.

RETRACEMENT by William Thiel, 1889.

Fir post (now missing) from which a:

48" Fir bears N2°E 167 lks.; now 65" stump in place, evidence of destroyed face remaining.

Bottom, S15E & N15W, bears South 0.50 lks.; in place.

Creek, 5 lks. wide, course N20W, bears South 140 lks.; in place.

Leave bottom, bears South 300 lks.; in place.

RESURVEY by Charles Slang in 1910.

18" x 20" x 10" Sandstone (missing) from which a:

14" Fir bears S60½W 294 lks.; missing, point falls in road.

10" Alder bears N54½W 282 lks.; missing, point falls in road.

RESTORED

Set 1½" x 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE BOARD OF FORESTRY T22S S23 S26 R12W S24 1969 RS359", 34 inches in ground, and from which a:

10" Alder bears N85½W 38.9 ft. to face; scribed T22S R12W S23 BT RS359.

9" Alder bears S3½W 54.0 ft. to face; scribed T22S R12W S26 BT.

Set 4" x 4" x 72" white painted Cedar post 2.4 ft. West of corner pipe. Oregon State Forestry Department metal location poster on 10" Alder N85½W.

Dated August 1, 1969.

Restored by

Lloyd David Smith
Lloyd David Smith, Transitman

under my direction.


FILE Present and witnessed by Charles W. Cook

RECEIVED

SEP 9 1969

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

#59



File No. 65/101-11