

RESTORED CORNER FOR STATE OF OREGON--DEPARTMENT OF FORESTRY

One quarter corner common to Sections 26 and 27, Township 22 South, Range 12 West, Willamette Meridian, Douglas County, Oregon.

ORIGINAL

6" Cherry (missing) from which a:

- 18" Fir bears N 85 W 40 lks.; now 50" windfall, exposed scribes 1/4 S BT.
- 8" Myrtle bears N 11 E 22 lks.; now 20" in clump of 9, inside honeycombed, axework visible.
- Spur top bears North 60 lks.; in place.

RESTORED

Set 1 1/2" x 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE BOARD OF FORESTRY 1/4 S26 S27 1969 RS 359", 34 inches in ground, and from which a:

- 18" Cedar bear S 62 E 39.6 ft. to face; scribed 1/4 S26 BT RS 359.
- 30" Myrtle bears S 70 W 51.9 ft. to face; scribed 1/4 S27 BT.
- 20" Myrtle (orig.) bears N 11 E 14.5 ft. to face; scribed BT.

Set 4" x 4" x 72" white painted Cedar post 1.8 ft. N 57 W of corner pipe. Oregon State Forestry Department metal location poster on 20" Myrtle BT N11E.


Dated March 6, 1969

Restored by *George Gresham* under my direction.
George Gresham, Transitman

FILED
RECEIVED

MAY 20 1969

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.



○ #56
Present and witnessed by David Brown
Roy Ball