



THE ROBERT DOLLAR CO.

FOREST PRODUCTS DIVISION

AREA CODE 503

TELEPHONES

832-2111 OFFICE ~~832-5050~~ SALES 832-5820

GLENDAL, OREGON

October 3, 1969

HEAD OFFICE
311 CALIFORNIA STREET
SAN FRANCISCO 4

County Surveyor's Office
Douglas County Courthouse
Roseburg, Oregon

Dear Sir:

During the past week I have renewed the following corners:

1/4 Sec. Cor. to Sec. 27 and 28, T 32 S, R4W -

SET 3/4" x 32" Iron Pipe

SCRIBED Yew Wood 16", S 14 $\frac{1}{2}$ ⁰ W, 29.2 ft. Mkd. T32S
R4W S 28 RS 841 BT

FOUND D.F. ^{opened at base mtd. 1/4} 24", N 83⁰ W, 7 Lks. blown down; D.F.
20", N 50⁰ E, 6 Lks. Good condition.

1/4 Sec. Cor. to Sec. ²⁸~~27~~ and 33, T32S, R4W -

SET 3/4" x 32" Iron Pipe

SCRIBED Madrone 10", N 19 $\frac{1}{2}$ ⁰ E, 16.6 ft. Mkd. T32S
R4W S 28 RS 841 BT
Madrone 5", S 78⁰ W, 11.0 ft. Mkd. T32S
R4W S 33 RS 841 BT

#107 ✓ FOUND D.F. 40", N 63⁰ W, 15 Lks. Stump

Sec. Cor. to 27, 28, 33, 34, T32S, R4W -

SET 3/4" x 32" Iron Pipe

FILED
RECEIVED

OCT 7 1969

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

C. S. File No. 55/129-1

SCRIBED D.F. 11½", S 41° E, 50.1 ft. Mkd. T32S R4W
S 34 RS 841 BT
D.F. 9", N 19° E, 48.5 ft. Mkd. T32S R4W
S 27 RS 841 BT
D.F. 12", N 45° W, 71.7 ft. Mkd. T32S R4W
S 28 RS 841 BT
Live Oak 4", S 40° W, 36.2 ft. Mkd. S 33 BT

#108 ✓

Sec. Cor. to 19, 20, 30, 29 T32S, R8W -

#105 ✓

SCRIBED Chinquapin 4" N 52° E 11.9 ft. Mkd. T32S
R8W S20 RS 841 BT

FOUND S.P. 12", S 18½° E, 32.1 ft.
Madrone 7", S 27° W, 27.8 ft.
D. Fir 8", N 41° 20' W, 13.2 ft.
Tan Oak 5" Broken off
1/8" Hex. Drill Steel

} See Ken. #22

All bearings were taken with a staff compass; mag. variation
19° 45' E. Distances were measured with a steel tape and the
work was witnessed by Marvin Van Norman.

Very truly yours,

THE ROBERT DOLLAR CO.

Ronald A. Brandt

Ronald A. Brandt
RS 841

RB/ab

FILED
RECEIVED

OCT 7 1969

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

C. S. File No. 55/129

The Robert Dollar Co.
Glendale, Ore. 97442

October 3, 1969

County Surveyor's Office
Douglas County Courthouse
Roseburg, Oregon

Dear Sir:

During the past week I have renewed the following corners:

1/4 Sec. Cor. to Sec. 27 and 28, T 32 S, R4W -

SET 3/4" x 32" Iron Pipe

SCRIBED: Yew Wood 16", S 14 $\frac{1}{2}$ ^o W, 29.2 ft. Mkd. T32S
R4W S 28 RS 841 BT

FOUND D.F. 24", N 83^o W, 7 Lks. blown down; D.F.
20", N 50^o E, 6 Lks. Good condition.

1/4 Sec. Cor. to Sec. ~~27~~²⁸ and 33, T32S, R4W -

SET 3/4" x 32" Iron Pipe

SCRIBED Madrone 10", N 19 $\frac{1}{2}$ ^o E, 16.6 ft. Mkd. T32S
R4W S 28 RS 841 BT
Madrone 5", S 78^o W, 11.0 ft. Mkd. T32S
R4W S 33 RS 841 BT

FOUND D.F. 40", N 63^o W, 15 Lks. Stump

Sec. Cor. to 27, 28, 33, 34, T32S, R4W -

SET 3/4" x 32" Iron Pipe

Additional Information

#106 $\frac{1}{4}$ Cor. To 27-28

original D.F. found { 24" now, N 50° E, 6 Iks. - Good Condition -
 20" orig.
 upper face opened about 15 yrs. earlier (1954) but I
 couldn't read any scribing.
 I opened a lower face (chopping in 2-3") and found
 the scribing $\frac{1}{4}$ S.

original D.F. found { 28" now, N 83° W, 7 Iks. - Blown Down -
 24" orig.
 I opened the face additionally and found the
 scribing $\frac{1}{4}$ S


#107 $\frac{1}{4}$ Cor. To 28-33

original D.F. found { 40" when cut, N 63° W, 15 Iks. - Low cut stump
 40" orig.
 opened prior to logging (about 1955) and some
 scribing remains on the stump reading
 partially B.T. and some scribing on a
 piece of wood layed by the stump
 reading $\frac{1}{4}$


FILED
 RECEIVED

OCT 13 1969

COUNTY SURVEYOR
 DOUGLAS COUNTY, ORE.



Ronald A. Brandt



SCRIBED D.F. 11½", S 41° E, 50.1 ft. Mkd. T32S R4W
S 34 RS 841 BT
D.F. 9", N 19° E, 48.5 ft. Mkd. T32S R4W
S 27 RS 841 BT
D.F. 12", N 45° W, 71.7 ft. Mkd. T32S R4W
S 28 RS 841 BT
Live Oak 4", S 40° W, 36.2 ft. Mkd. S 33 BT

Sec. Cor. to 19, 20, 30, 29 T32S, R8W -

SCRIBED Chinquapin 4" N 52° E 11.9 ft. Mkd. T32S
R8W S20 RS 841 BT

FOUND S.P. 12", S 18½° E, 32.1 ft.
Madrone 7", S 27° W, 27.8 ft.
D. Fir 8", N 41° 20' W, 13.2 ft.
Tan Oak 5" Broken off
¼" Hex. Drill Steel

All bearings were taken with a staff compass; mag. variation
19° 45' E. Distances were measured with a steel tape and the
work was witnessed by Marvin Van Norman.

Very truly yours,

THE ROBERT DOLLAR CO.

Ronald A. Brandt

Ronald A. Brandt
RS 841

RB/ab

#108 Sec. Cor. To 27, 28, 33, 34, T 32S, R 4W

Found the remains of -

original Dead D.F. 14", S 86° E, 44 lks.

The snag had broken off at the ground and left a distinct stump. Scribing on the felled portion

read S 34, B.T. Using the above bearing

and distance the pipe was set.

Sec. Cor. To 19, 20, 30, 29 T 32S, R 8W

Bearings, Distances, and

B.T.'s found and listed on

this sheet are those

tree sizes of the
the opposite side of
I measured.

REGISTERED
OREGON
LAND SURVEYOR

Ronald A. Brandt

JULY 12, 1968
RONALD A. BRANDT
844

FILED
RECEIVED

OCT 12 1969

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.