


CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established in 1899 by Henry L. Chandler, C.S.
Re-established in 1968 by County Surveyor



Description of corner evidence found:

Found original fir - scribing visible
Brass cap set by C.S. in 1958 mkd (1968)



Brass cap 1.2 ft west of true corner

CS from which

- 10" fir snag brs. N30E 11.9 ft - scribing visible (orig)
- 36" fir brs. S51W 12.5 ft - face chopped out (orig)
- 18" snag brs. N39W 10.6 ft - face chopped out (orig)
- 20" fir brs. N71W 12.0 ft - scribing visible - with tag
- 36" fir brs. S51W 12.5 ft - scribing visible - with tag
- 16" fir brs. N89E 28.9 ft - scribing visible - with tag
- 40" fir brs. S65E 48.5 ft - scribing visible - with tag

Description of monument and accessories established to perpetuate the original location of this corner

No new monument set

Set 2 fence posts with signs + 5 ft north facing west
+ 5 ft west facing north

Office of SURVEY County of DOUGLAS
State of ORE, I hereby certify that the within instrument was filed in this office
for record on the 1ST day of MAY, 1970, at 9 o'clock Am., (signed)

FILED
RECEIVED

J. M. W. Ryan
(COUNTY OFFICIAL)

by _____ (DEPUTY)

REGISTERED
OREGON
LAND SURVEYOR

Tom O. McCulloch
JULY 10, 1964
TOM O. McCULLOUGH
650

MAY 11 1970

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.
Form R6-7100-57 (9/66)