

RESTORED CORNER FOR STATE OF OREGON--DEPARTMENT OF FORESTRY

One quarter corner common to Sections 26 and 35, T22S, R12W, W.M., Douglas County, Oregon.

ORIGINAL

Cedar Post (missing) from which a:

- 8" Spruce bears S03°W 40 lks.; now missing.
- 24" Fir bears N32°W 6 lks.; now 60" stump, in place, scribe / visible on exposed face.

RESTORATION by Wilford N. Haines (No record found, date unknown-- in a telephone conversation Mr. Haines stated he had filed this corner)

1" Tee bar (found in place) from which a:

- 40" Hemlock bears S08°W 24.8 ft. to face; in place, face open, scribes $\frac{1}{2}$ S35 BT visible.
- 53" Hemlock bears N61°W 48.7 ft. to face; in place, face closed.

RESTORED


Set 1½" x 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE BOARD OF FORESTRY $\frac{1}{2}$ S26 S35 1970 RS359", 34 inches in ground, over 1" Tee bar, and from which a:

- 46" Fir bears N31°W 51.8 ft. to face; scribed $\frac{1}{2}$ S26 BT RS359.

Set 4" x 4" x 72" white painted Cedar post 1.2 ft. N22°W of corner pipe. Oregon State Forestry Department metal location poster on 46" Fir BT N31°W 51.8 ft.

Dated May 22, 1970

Restored by Lloyd D. Smith under my direction.
Lloyd D. Smith, Transitman



Present and witnessed by Steven F. Howard

FILED
RECEIVED

JUN 17 1970

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.