

SURVEY NO. _____

SURVEY NARRATIVE to comply with Paragraph 209.250, O. R. S.

SURVEY FOR: MR. BEN CORWIN
Box 127
Glendale, Oregon

PURPOSE: To survey and monument a parcel of land in the Southeast 1/4 of Section 2, Township 33 South, Range 7 West, Willamette Meridian, Douglas County, Oregon.

PROCEDURE: Since the Douglas County Surveyor's Records show that the North 1/4 Corner of Section 2 was not set in the Original Survey, we began a random traverse from the Northeast Section Corner toward the Northwest Section Corner along the North line of Section 2.

At a point South $89^{\circ}25'40''$ West 714.03 feet we found the Corner for Sections 35 and 36; and at North $88^{\circ}59'52''$ West 4534.25 feet from this point we found the Section Corner between Sections 2 and 3. We set the North 1/4 Corner of Section 2 at the proportionate distance between the Northeast and Northwest Section Corners of Section 2 and on line between the Section Corner for Sections 35 and 36 and the Northwest Corner of Section 2. From this point we found an Iron Pipe which bears North $9^{\circ}33'$ West 17.28 feet. No evidence of the South 1/4 Corner of Section 35 was found.

Ran random lines from the North 1/4 Corner and the South 1/4 Corner and from the East 1/4 Corner to the West 1/4 Corner, setting the Center 1/4 and 1/16 Corners, with details as shown on plat and in accordance with regulations of Manual of Instructions for Survey of Public Lands.

Corners on East side of Section set by R.S. 404 have been replaced by B.L.M.

FILED *LL*
RECEIVED

APR 9 1971

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

REGISTERED
OREGON
LAND SURVEYOR

Claude E. Masters

OCTOBER 24, 1958
CLAUDE E. MASTERS
457

C.S. File 55-192A

Map File M 41-39

CLAUDE E. MASTERS
Professional Land Surveyor
344 Valley View Road
Grants Pass, Oregon 97526

April 15, 1971.

Mr. J. W. Byron, County Surveyor
Court House
Roseburg, Oregon 97470


Dear Mr. Byron:-

Regarding the North $\frac{1}{2}$ Corner of Sec. 2, T. 33 S., R. 7
W., W. M. my error was in not designating the corner set
as a temporary corner. My client needs only the North
South Centerline of the Section.

I anticipate being in that area before too long and
could probably set the correct closing corner.
However, I don't have the notes for the Southeast Corner
of Section 34 - 32 - 7.

Next time I am in Roseburg I will try to pick them up.

Sincerely,



FILED
RECEIVED

APR 19 1971

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

C.S. File No. 55/192b