


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Never set




Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner

At the properly proportioned position I placed a 2" x 36" galvanized iron pipe, flanged at the bottom and capped with a bronze disk welded on top. The monument projects 6" above ground. I filled in around the pipe monument with stone and packed earth.

I stamped the disk



I established new bearing trees as follows, Each bearing tree has a scribed face and a U.S.F.S. bearing tree sign breast high and facing the monument.

Bearing trees set:

- a 62" fir bears S 23° E 36.55 feet
- a 54" fir bears N 5° E 13.50 feet

James W. [Signature]

Office of County Surveyor County of Douglas
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 24 day of June, 1971, at 11 o'clock A.m., (signed)
James W. [Signature] by _____
 (COUNTY OFFICIAL) (DEPUTY)

CORNER #17 ON MAP

C.S. File 55/201-12

Map File M 41-77