

RESTORED CORNER FOR STATE OF OREGON--DEPARTMENT OF FORESTRY

One quarter corner common to Sections 8 and 9, Township 22 South, Range 11 West, W.M., Douglas County, Oregon.

ORIGINAL

No evidence of original corner found.

REESTABLISHMENT by Warren D. Hootman, 1958

Iron pipe (missing) from which a:

- 20" Fir bears N64°E 28.2 ft.; now 21", scribe marks visible in partially closed face.
- 22" Fir bears S48°W 2.0 ft.; now 26", scribes 1S visible in partially closed face.

RESTORED



Set 1½" x 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE BOARD OF FORESTRY 1/4 S8 S9 1971 RS359", 34 inches in ground, and from which a:

- 27" Fir bears S03½°W 92.7 ft. to face; scribed 1/4 S8 BT RS359.
- 21" Fir bears N34½°E 73.5 ft. to face; scribed 1/4 S9 BT.

Set 4" x 4" x 72" white painted Cedar post 3.5 ft. N21°E of corner pipe. Oregon State Forestry Department metal location poster on 21" Fir BT N34½°E 73.5 ft. Also poster on 26" Fir BT (Hootman) S48°W 2.0 ft. Ren #17

Dated October 27, 1971

Restored by Charles W. Cook under my direction.
Charles W. Cook, Engineer



Present and witnessed by Kenneth L. Graham
William A. Bodewig
Raymond S. Craig

FILED
RECEIVED

FEB 3 1972

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

O #114

C. S. File No. 55/233-7