

RESTORED CORNER FOR STATE OF OREGON--DEPARTMENT OF FORESTRY

One quarter corner common to Sections 25 and 36, Township 22 South, Range 11 West, W.M., Douglas County, Oregon.

ORIGINAL

4" Fir (now rotted fir root system in place) from which a:

- 10" Fir bears N50°W 12 lks.; now 32", face grown over (N30W).
- 50" Burnt Fir bears S87°E 18 lks.; now in place, scribes 1/ visible in rotted face.

RESTORED

Set 1½" x 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE BOARD OF FORESTRY 1/4 S25 S36 1971 RS359", 34 inches in ground, and from which a:



- 22" Fir bears N3½°W 19.9 ft. to face; scribed 1/4 S25 BT.
- 22" Fir bears S48°W 13.9 ft. to face; scribed 1/4 S36 BT RS359.

Set 4" x 4" x 72" white painted Cedar post 2.1 ft. S71°W of corner pipe. Oregon State Forestry Department metal location poster on 22" Fir BT, N3½°W.

Dated November 22, 1971

Restored by Charles W. Cook
Charles W. Cook, Engineer

under my direction.



Present and witnessed by Dale E. Redding
William A. Bodewig
Kenneth L. Graham

FILED
RECEIVED

FEB 3 1972

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

o #115

C. S. File No. 55/233-7