

# ROSEBURG

---

## LUMBER CO.

P.O. BOX 1088 · ROSEBURG, OREGON 97470    PHONE (503) 679-8741

October 29, 1973

County Surveyor  
Douglas County Court House  
Roseburg, OR 97470

Dear Sir:

I have scribed a new bearing tree and placed a 5/8" by 30" long iron rod along side the stone for the 1/4 corner for Sections 27 and 34 T. 26S. R. 1W. W.M. in the Glide District of the Umpqua National Forest.

Found:

8"x10"x10" stone. I set a 5/8"x30" I.R along side the stone.

36" Fir N 14° W - 19 Lks. scribe visible


12" Fir S 7° E - 51 Lks. scribe visible (now a stump which has been pushed out of place by a cat.)

Scribed:

12" Hemlock S 22° E 81.5 ft. "1/4 S 34 BT"

Yours truly,

ROSEBURG LUMBER CO.






Howard W. Johnstone  
Logging Engineer

HWJ/am

FILED  
RECEIVED

OCT 3 1973

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.



C. S. File No. 55/320

7/11  
c #681  
o