

Ronald A. Brandt, P.E. 6803
P.O. Box 427,
Glendale, Oregon 97442

September 24, 1973

NARRATIVE OF LAND SURVEY

in the NE 1/4, Sec. 31 and the W 1/2, NW 1/4, Section 32, T. 32 S., R. 6 W., W.M., Douglas County, Oregon.

Survey for- Mr. and Mrs. James D. Chitwood
Glendale, Oregon 97442

PURPOSE: to minor partition Parcel 1 of the land survey of record in file M 28-68 at the Douglas County Land Surveyor's Office into two parcels of approximately equal size;

METHOD: done in conjunction with land survey of record found in file M 49-37 and c.s. 55/314 using closed-random transit traverse techniques about the area;

EQUIPMENT: this work was conducted with a 30 second Gurley Transit and a Lufkin 300 ft. steel tape with 100 th ft. divisions;

INDIVIDUALS AND DATES: this specific portion of survey was initiated Sept. 3 and completed Sept. 22, 1973 with witnesses being James Chitwood, Charles Dehn, Joseph Larson, and occupants on properties adjacent;

REFERENCES: on record in Douglas County Land Surveyor's Office, Roseburg, Oregon are surveys in files M 28-68, M 49-37 and c.s. 55/314 all containing pertinent information; deed records of properties were also referred;

CORNERS FOUND:

1. SW Corner, found a 1" Iron pipe on the Southern Pacific Railroad boundary;
2. NW Corner, found a 3/4" Iron pipe 12" high located on County Road No. 27, south boundary, said pipe in position N 18° 30' 28" E, 2230.67' from the EC 1/16 Corner, Section 31;
3. NE Corner, found a 5/8" Iron rod, by Shaner, on the south boundary of said county road;
4. East line point, found a 5/8" Iron rod, by Shaner, set on top of a low landfill dike;

CORNERS SET:


1. North Point on division line, set a 1" x 36" Iron rod, 4" high on the south boundary of County Road No. 27, with boundary position determined using angular and distance relationships of M 28-68, said point located N 29° 41' 11" E, 2228.73' from the EC 1/16 Corner, Section 31;
2. Line point on the division line, set a 1" x 36" Iron rod, 4" high, in position on the low landfill dike;

-DESCRIPTIONS ON PAGE II OF NARRATIVE-

FILED
RECEIVED

SEP 26 1973

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.



C. S. File No. 55/326 A

Ronald A. Brandt, P.E. 6803
 P.O. Box 427,
 Glendale, Oregon 97442

Sept. 24, 1973

DESCRIPTIONS:

A. Parcel 1a.

BEGINNING at a 3/4" Iron pipe located N 18° 30' 28" E, 2230.67' from the EC 1/16 Corner, Section 31, T. 32 S., R. 6 W., W.M., said pipe on the south boundary of County Road No. 27 (No. Reuben Road);

thence S 00° 11' 06" E, 656.01' to a 1" Iron pipe on the northeasterly boundary of Southern Pacific Railroad Property;

thence S 43° 26' 58" E, 119.85' following said railroad boundary to a point at the centerline of Cow Cr.;

thence N 52° 36' 13" E, 98.38' to a point at the centerline of Cow Cr.;

thence N 85° 46' E, 89.89' to a point at the centerline of Cow Cr.;

thence S 71° 48' 27" E, 150.89' to a point at the centerline of Cow Cr.;

thence NORTH, 145.54' to a 1" Iron rod in position on a low landfill dike;

thence NORTH, 399.12' to a 1" Iron rod on the south boundary of County Road No. 27;

thence N 68° 36' 18" W, 143.70' to a point on said south boundary of road;

thence N 64° 11' 18" W, 290.91' to the POINT OF BEGINNING;

containing more-or-less 5.47 acres all in the NE 1/4, said Section 31, Douglas County, Oregon.

B. Parcel 1b.

BEGINNING at a 1" Iron rod located N 29° 41' 11" E, 2228.73' from the EC 1/16 Corner, Section 31, T. 32 S., R. 6 W., W.M., said point on the south boundary of County Road No. 27 (No. Reuben Road);

thence SOUTH, 399.12' to a 1" Iron rod in position on a low landfill dike;

thence SOUTH, 145.54' to a point at the centerline of Cow Cr.;

thence S 71° 48' 27" E, 212.04' to a point at the centerline of Cow Cr., said point on the section line of Sections 31 and 32;

thence S 77° 54' 02" E, 242.98' to a point at the centerline of Cow Cr.;

thence N 00° 11' 11" W, 234.73' to a 5/8" Iron rod in position on a low landfill dike;

thence N 00° 11' 11" W, 299.36' to a 5/8" Iron rod on the south boundary of County Road No. 27;

thence N 75° 16' 18" W, 349.89' to a point on said south road boundary;


thence N 68° 36' 18" W, 106.22' to the POINT OF BEGINNING;

containing more-or-less 5.44 acres located in Sections 31 and 32, T. 32 S., R. 6 W., W.M., Douglas County, Oregon .

FILED
 RECEIVED

SEP 26 1973

COUNTY SURVEYOR
 DOUGLAS COUNTY, ORE



C. S. File No. 55/326.6