

S U R V E Y   N A R R A T I V E

Location: Sections 26, 27 and 34, T. 27 S., R. 6 W., W.M.  
Section 3, T. 28 S., R. 6 W., W.M. Douglas County, Oregon

Surveyed for: S.O. Cable T.V., 926 So. Grape Street, Medford, Ore. 97501

Purpose: To survey and monument the location of a buried cable  
across the Christensen Brothers ranch and prepare a legal  
description for a right of way agreement.

Procedure:

Commencing at the Quarter corner common to Sections 26 and 27 which is  
monumented with an iron pipe with a brass cap marked:

County Surveyor's Office , 1961

$\frac{1}{4}$  S27 ; S26 T27S R6W

from which:

A White Oak, 12 inches in diam. bears S.  $81^{\circ}$  E, 25.8 feet dist.  
mkd.  $\frac{1}{4}$  S26 CS BT.

A Black Oak, 12 inches in diam. bears N.  $87^{\circ}$  W., 30.6 ft. dist.  
mkd.  $\frac{1}{4}$  S27 CS BT.


Thence N.  $00^{\circ}39'56''$ W. along the east line of Section 27 for 1321.41  
feet to the established 1/6th Section corner which is monumented with  
an iron pipe,  $1\frac{1}{2}$  inches in diameter located at an old fence corner,  
and shown on Survey No. M 38-66 executed by RLS No. 750.

I then set 5/8 inch diameter iron rods, 30 inches in length along  
the general course of the underground television cable as shown on the  
accompanying plat, said rods having a yellow plastic cap marked;

TEMPLIN  
RE 3024

The survey was terminated at Station 116 + 53.74 which is the location  
of existing power pole No. B 7605.

All bearings are referred to the true meridian based upon solar observations  
taken at the beginning and end of the survey. Survey executed with A  
Wild-T16 transit theodolite and a K and E Microranger electronic distance  
measurement instrument.



RICHARD E. TEMPLIN  
Consulting Engineer  
715 N. E. SIXTH ST.  
MEDFORD, ORE. 97526

FILED  
RECEIVED

JAN 28 1974

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.