


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

NONE



Description of corner evidence found:

NONE



Description of monument and accessories I established to perpetuate the original location of this corner

I set a 36-inch long, 2 1/2 inch galvanized iron pipe 32 inches in the ground, in a mound of stones, with a 4-inch brass cap marked:

Bearing trees:

W 1/16 S 22  
RLS 536 1974

a cedar, 11 inches diameter bears S 57° W  
12.9 feet scribed W 1/16 S 22 (BT) with a  
brass washer stamped RLS 536

a white fir, 10 inches diameter bears S 72 1/2° E  
21.6 feet scribed W 1/16 S 22 (BT) with a  
brass washer stamped RLS 536

Corner lies on Southwest slope approximately 95 feet East of old skid Road.

From Book #6, page 20, Tiller Land Survey #13 - Contract #004346N.

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the ..... day of ....., 19....., at..... o'clock .....m., (signed)  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

FILED  
RECEIVED *See*  
*M 49-69*  
AUG 8 1974

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.