

RESTORED CORNER FOR STATE OF OREGON-DEPARTMENT OF FORESTRY

Angle Point corner for Section 25, Township 22 South, Range 12 West, W.M., Douglas County, Oregon (Original East 1/4 25).

ORIGINAL

14" X 10" X 6" Stone (missing) from which a:

- 8" Cedar bears S65°W 25 lks.; now 19", in place, face buried by side cast debris from Road construction, excavated 7.0 ft. to face, scribes BT exposed.
- 6" Chittum bears S22°E 29 lks.; missing.
- 10" Linetree bears North 373 lks.; in place.
- Ridge, course East, bears North 360 lks.; in place.

RESTORATION by A. G. Gibson, 1961.

1 1/2" X 36" galvanized iron pipe with 3" bronze cap (missing covered by road construction) from which a:

- 30" cedar bears N26°W 45.9 ft.; now 22" in place, face now buried by sidecast debris, and inaccessible.
- 22" cedar bears N49 1/2°W 25.4 ft.; now 18" in place, face buried by sidecast debris, and inaccessible.

RESTORED

Set 1 1/2" X 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE BOARD OF FORESTRY T22S S25 R12W AP 1974 RS359", 35 inches in ground, in fill section of road, and from which a:


- 19" Cedar (orig. 8") bears S65°W 16.5 ft. to face; scribed RS359 (7.0 ft. above old face).
- 22" Cedar bears N26°W 46.5 ft. to face; scribed APS 25 BT (at new ground level).

Set 4" X 4" X 72" white painted Cedar post 8.0 ft. S47°E of corner pipe. Oregon State forestry Department metal location poster on 22" Cedar BT N26°W 46.5 ft.

Dated June 18, 1974.

Restored by William E. Metcalf under my direction.  
William E. Metcalf, Engineer

Present and witnessed by Anthony J. Klosterman  
James L. Shumway  
Barbara A. Smith



\* 133 T22-11 ✓  
\* 116 T22-12 ✓

57/4-1 e