

3r 25-75

T24S R6W

S2 | S1

S11 | S12

SEE RENEWAL #104

FOUNDS:

BRASS CAP SET BY GARRETT

MARKED T24S R6W

S2 | S1

S11 | S17

1973

FROM WHICH A

WHITE OAK 7" DIA BEARS N32°E 25¹/₂ FT

SCRIBED S1 T24S R6W

WHITE OAK 8" DIA BEARS S82°E 26¹/₂ FT

SCRIBED S12 T24S R6W

WHITE OAK 6" DIA BEARS S21°W 19¹/₂ FT

SCRIBED S11 T24S R6W

WHITE OAK 6" DIA BEARS N34°W 22¹/₂ FT

SCRIBED S2 T24S R6W

#108 ✓

DIETZGEN NO. 3895-6

BRASS CAP SET BY BLM.

MARKED

T24S R6W

S 2	S 1
<hr/>	
S 11	S 12
19 73	

FROM WHICH

A FIR 7" DIA. BEARS N 47° E 29.4'
(REC. N 49° E) SCRIBED T24S R6W S1 BT

A FIR 7" DIA. BEARS S 88° E 31.0'
(REC. S 86° E) SCRIBED T24S R6W S12 BT

A FIR 6" DIA. BEARS S 26° W 23.1'
(REC. S 27° W) SCRIBED T24S R6W S11 BT

A WHITE OAK 7" DIA. BEARS N 12° W 13.6'
(REC. N 10° W) SCRIBED T24S R6W S2 BT

BRASS CAP SET BY GARRETT
S 11 1/2° W 3.55' (REC. S 13 1/2° W 3.66')

SET

REMOVE BRASS CAP SET BY
GARRETT (PROPORTIONED), AND

REPLACE WITH 5/8" IRON ROD 4 INCHES
ABOVE GROUND,


U.S. FILE NO. 57/21-1

Harry P. Mearns

P.L. EARLE PAGE 2

OK [Signature]

DIETZGEN NO. 385-6



COUNTY OF DOUGLAS
OFFICE OF THE SURVEYOR
ROSEBURG, OREGON 97470

February 28, 1975

William W. Glenn, Chief
Branch of Cadastral Engineers
P. O. Box 2965
Portland, OR 97208

Dear Mr. Glenn:

Our office has had an inquiry about the corner for
Sections 2 - 1 - 11 - 12 of T. 24 S., R. 6 W.

A surveyor has found two brass caps 3 1/2 feet apart
and nine bearing trees. Don E. Garrett, a private
surveyor, set the corner by proportionate measurement
in a survey he did in September, 1973. He marked
four bearing trees. The BLM brass cap is marked October,
1973 and four more bearing trees were marked. The other
tree is evidently an original BT.

Would you please send to us a copy of your field notes
for that 1973 survey.

Thank you,

Francis L. Ingram
Francis L. "Fritz" Ingram
Douglas County Surveyor

vy