


PUBLIC LAND CORNERS

FILED
RECEIVED

JUN 3 1981

WEYERHAEUSER COMPANY COUNTY SURVEYOR
 SPRINGFIELD BRANCH DOUGLAS COUNTY, ORE.



TOWNSHIP 23 S RANGE 4 W
 SECTION 12 CORNER CW 1/16 "J"
 COUNTY Douglas OREGON

GLO SURVEY RECORD

DATE: _____
 CORNER Not set by GLO

ACCESSORIES:

BEARING-	LINKS-	FEET-

PRESENT CONDITION - (DESCRIBE FULLY USE PAGE 2 IF NEEDED FOR EXPLANATION.)

W. N. Haines SURVEY RECORD
 DATE: Nov. 1963

Transit Survey
 Set "T" iron and scribe:
 12" Incense Cedar S 26 W 15.0
 6" White Fir N 54 E 9.0

PRESENT CONDITION:


Found "T" iron in place
 12" Incense Cedar- scribing visible
 6" White Fir, bark scribed.

CORNER SET: "T" iron as set by Haines Survey MAG. DECL.: 20 degrees F

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-	SURVEY-	
S 26 W	14.7	Haines 63	To scribed face
N 52 E	9.0	"	To center of free.

SECTION 12 TOWNSHIP 23 S RANGE 4 W



FILED
RECEIVED
JUN 3 1981
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

—// // //— LINE MARKED BY NOTCH CUT IN BLAZE.

○ KNOWN CORNER.

⊗ REFERENCED CORNER
BY WEYERHAEUSER
METHOD.

ACCESSORIES ADDED THIS DATE:

MAGNETIC DECLINATION 20 Degrees

	BEARING	FEET	ORIG. B.T.	"W" NAIL	PLATE	BRASS DISC
36" Incense Cedar	N 13 W	26.4	---	X	X	---
46" Fir	S 5 W	9.7	---	X	X	---

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: In old growth stand.

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) S 75 W ON MINUS (-) 52 %

NORTH: + 10% for 50' to top of spur C-NW

SOUTH: - 10%

EAST: + 48%

WEST: - 40%

FROM CORNER |

FILED
RECEIVED

JUN 3 1981

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE

WORK DONE FOR W. CO.

FIELD NOTES IN BOOK:

By: Glen McChesney DATE: 8/9/68

~~ENGINEER SURVEYOR~~

ASSISTED BY:

UNDER THE SUPERVISION OF:

COPIES SENT TO:

SEAL

PAGE 3

C. S. File No. 58/B

36	31	32	33	34	35	36	31
1	6	5	4	3	2	1	6
12	7	8	9	10	11	12	7
13	18	17	16	15	14	13	18
24	19	20	21	22	23	24	19
25	30	29	28	27	26	25	30
36	31	32	33	34	35	36	31
1	6	5	4	3	2	1	6

WEYERHAEUSER COMPANY

CORNER REFERENCE METHOD CONSISTS OF:

A "W" NAIL DRIVEN THRU THE HOLE IN A BRASS DISC, INTO A NOTCH CUT LOW ON A TREE, STAMPED WITH THE OREGON REGISTERED LAND SURVEYOR OR PROFESSIONAL ENGINEER REGISTRATION NUMBER.

AN EMBOSSED ALUMINUM PLATE, NAILED HEAD HIGH ON SAME TREE WITH 8D ALUMINUM NAILS, WITH DISTANCE AND BEARING FROM THE "W" NAIL TO THE CORNER STAMPED ON IT.

