


PUBLIC LAND CORNERS

WEYERHAEUSER COMPANY
 SPRINGFIELD BRANCH

TOWNSHIP 23S RANGE 4W
 SECTION 33 CORNER N $\frac{1}{2}$
 COUNTY Douglas OREGON



<p>GLO SURVEY RECORD</p> <p>CORNER <u>post</u> DATE: <u>1855</u></p>	<p>PRESENT CONDITION - (DESCRIBE FULLY - USE PAGE 2 IF NEEDED FOR EXPLANATION.)</p> <p><u>No trace</u></p>																																								
<p>ACCESSORIES:</p> <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width:15%;">BEARING-</th> <th style="width:15%;">LINKS-</th> <th style="width:15%;">FEET-</th> <th style="width:55%;"></th> </tr> </thead> <tbody> <tr> <td><u>18" Fir</u></td> <td><u>N15E</u></td> <td><u>57</u></td> <td><u>33.0</u></td> </tr> <tr> <td><u>3" Fir</u></td> <td><u>S34E</u></td> <td><u>73</u></td> <td><u>42.8</u></td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		BEARING-	LINKS-	FEET-		<u>18" Fir</u>	<u>N15E</u>	<u>57</u>	<u>33.0</u>	<u>3" Fir</u>	<u>S34E</u>	<u>73</u>	<u>42.8</u>																												
BEARING-	LINKS-	FEET-																																							
<u>18" Fir</u>	<u>N15E</u>	<u>57</u>	<u>33.0</u>																																						
<u>3" Fir</u>	<u>S34E</u>	<u>73</u>	<u>42.8</u>																																						
<p>Douglas County SURVEY RECORD</p> <p>Found NE BT, iron bar set by <u>Thiel & T iron set by Haines.</u> DATE: <u>1983</u> (#78)</p> <p>Rescribe <u>42" Fir N15E 33.0'</u></p> <p><u>No other trees near.</u></p>	<p>PRESENT CONDITION:</p> <p><u>Found iron bar and T iron alongside.</u></p> <p><u>Found scribing in fire charred face.</u></p>																																								


CORNER SET: Iron bar as found MAG. DECL.: 20°

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-	SURVEY -	
<u>N15E</u>	<u>33.0</u>	<u>1855</u>	

#156 ✓

SECTION 33 TOWNSHIP 23S RANGE 4W



/// /// /// LINE MARKED BY NOTCH CUT IN BLAZE.

○--- KNOWN CORNER.

⊗--- REFERENCED CORNER
BY WEYERHAEUSER
METHOD.

Old Iron Bar set by Thiel and charred rescribing on NE Fir BT as found by
Douglas County Surveyors 1963 renewal crew is supported by G. Langdons
affadavit in CS File No. 53/9.

ACCESSORIES ADDED THIS DATE:

MAGNETIC DECLINATION 20°

1 only	BEARING	FEET	ORIG. B. T.	"W" NAIL	PLATE	BRASS DISC
10" Madronne	West	21.0	---	X	X	---

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: Brush, currently being cleared

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) _____ ON MINUS (-) _____ %

NORTH: Corner point is about 1' east of fence corner, fenced to West & to South.

FROM CORNER ↓

SOUTH: _____

EAST: _____

WEST: _____

WORK DONE FOR W. CO. _____

FIELD NOTES IN BOOK: _____

BY: Glen McChesney DATE: 4/ 5/1976
Project XXXXXXXXXX
ENGINEER - SURVEYOR

UNDER THE SUPERVISION OF:

REGISTERED PROFESSIONAL LAND SURVEYOR

Frank O. Williams

OREGON
JULY 12, 1906
FRANK O. WILLIAMS
0872

ASSISTED BY: _____

COPIES SENT TO: _____

SEAL

36	31	32	33	34	35	36	31
1	6	5	4	3	2	1	6
12	7	8	9	10	11	12	7
13	18	17	16	15	14	13	18
24	19	20	21	22	23	24	19
25	30	29	28	27	26	25	30
36	31	32	33	34	35	36	31
1	6	5	4	3	2	1	6

WEYERHAEUSER COMPANY

CORNER REFERENCE METHOD CONSISTS OF:

A "W" NAIL DRIVEN THRU THE HOLE IN A BRASS DISC, INTO A NOTCH CUT LOW ON A TREE, STAMPED WITH THE OREGON REGISTERED LAND SURVEYOR OR PROFESSIONAL ENGINEER REGISTRATION NUMBER.

AN EMBOSSED ALUMINUM PLATE, NAILED HEAD HIGH ON SAME TREE WITH 8D ALUMINUM NAILS, WITH DISTANCE AND BEARING FROM THE "W" NAIL TO THE CORNER STAMPED ON IT.

