


PUBLIC LAND CORNERS

FILED RECEIVED *JK*

DEC 22 1980

WEYERHAEUSER COMPANY COUNTY SURVEYOR
 SPRINGFIELD BRANCH DOUGLAS COUNTY, ORE.



TOWNSHIP 24S RANGE 1W

SECTION 28 CORNER CW 1/16 "J"

COUNTY Douglas OREGON

GLO SURVEY RECORD

CORNER DATE:

PRESENT CONDITION - (DESCRIBE FULLY - USE PAGE 2 IF NEEDED FOR EXPLANATION.)

ACCESSORIES:

	BEARING-	LINKS-	FEET-

T. E. Shrum, Jr. SURVEY RECORD
 DATE: June 1967
 Survey for U. S. Plywood - Champion Papers, Inc.
 Set 2½" aluminum cap
 10" Hemlock N6E 6.0' (1 BT only)
 CS File M36-13

PRESENT CONDITION:
 Found cap in place.
 12" Hemlock - scribing visible, U.S. Plywood tag.

CORNER SET: XXX 2½" aluminum cap as found MAG. DECL.: 20°E

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-	SURVEY-	
N5E	6.0	1967	Center measurement; 5.7' to face.

ACCESSORIES ADDED THIS DATE:

MAGNETIC DECLINATION

20°E

	BEARING	FEET	ORIG. B.T.	"W" NAIL	PLATE	BRASS DISC
36" Fir Stump	S17W	14.5	---	X	X	---
*26" Fir	N58½W	15.7	---	X	X	---
*Found U.S. Plywood tag on ground from this tree; renailed to tree.						

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: Logged to South; to be logged soon to North.

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) N45E ON MINUS (-) 55 %

FROM CORNER |

NORTH: - 30%

SOUTH: + 40%

EAST: - 50% approx. 100' to creek course North.

WEST: +48%

WORK DONE FOR W. CO. _____

FIELD NOTES IN BOOK: _____

BY: Glen Mc Chesney DATE: 10/21/1977
Project ENGINEER - SURVEYOR XXXXXXXXXX

UNDER THE SUPERVISION OF:

REGISTERED PROFESSIONAL LAND SURVEYOR

Frank O. Williams

OREGON JULY 12, 1969
FRANK O. WILLIAMS
0875

ASSISTED BY: _____

COPIES SENT TO: _____

FILED RECEIVED *JK*
DEC 22 1980
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE

SEAL

36	31	32	33	34	35	36	31
1	6	5	4	3	2	1	6
12	7	8	9	10	11	12	7
13	18	17	16	15	14	13	18
24	19	20	21	22	23	24	19
25	30	29	28	27	26	25	30
36	31	32	33	34	35	36	31
1	6	5	4	3	2	1	6

WEYERHAEUSER COMPANY

CORNER REFERENCE METHOD CONSISTS OF:

A "W" NAIL DRIVEN THRU THE HOLE IN A BRASS DISC, INTO A NOTCH CUT LOW ON A TREE, STAMPED WITH THE OREGON REGISTERED LAND SURVEYOR OR PROFESSIONAL ENGINEER REGISTRATION NUMBER.

AN EMBOSSED ALUMINUM PLATE, NAILED HEAD HIGH ON SAME TREE WITH 8D ALUMINUM NAILS, WITH DISTANCE AND BEARING FROM THE "W" NAIL TO THE CORNER STAMPED ON IT.

