

FILED

RECEIVED 24

NOV 18 1974

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

RESTORED CORNER FOR STATE OF OREGON--DEPARTMENT OF FORESTRY

One quarter corner common to Sections 8 and 9, T32S, R6W, W.M., Douglas County, Oregon.

ORIGINAL

Laurel post (missing) from which a:

- 36" Fir bears S70°E 25 lks.; now 24"x5 ft. high rotted stub, knocked downhill by windfall.
- 40" Fir bears N60°W 39 lks.; now 46" burnt stump in place, axe work on face visible, bark scribes eroded away.

RESTORED



Set 1-1/2"x36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE BOARD OF FORESTRY 1/4 S8 S9 1974 RS359", 34 inches in ground in mound of rock, and from which a:

- 46" Crig. Fir (stump) bears N60°W 25.7 ft. to face; bark scribed 1/4 S8 BT.
- 23" Fir bears N05-1/2°E 53.9 ft. to face; scribed 1/4 S9 BT RS359.

Set 4"x4"x72" white painted Cedar post N76W 10.2 ft. from corner pipe. Oregon State Forestry Department metal location poster on 23" Fir BT N05-1/2°E 53.9 ft.

Dated October 8, 1974

Restored by Lloyd D. Smith under my direction.
Lloyd D. Smith, Engineer



Present and witnessed by William E. Metcalf
Anthony J. Klosterman

#138 ✓

D.S. File No. 58/18