

FILED

RECEIVED *WJ*

JUL 1 1976

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

REWITNESSED CORNER FOR STATE OF OREGON--DEPARTMENT OF FORESTRY

Section corner common to Sections 3 and 10, (West Side), T22S, R11W, W.M.,
Douglas County, Oregon.

ORIGINAL

Stone 12" x 10" x 7" (found in place, 5 notches on S and 3 notches on E -
see restoration below) from which a:

12" Dead Cedar bears N30°E 22 lks.; missing.

RESURVEY by William Whipple, 1893

4" Willow bears N74°E 10 lks.; missing.
3" Alder bears S31°W 50 lks.; missing.
5" Willow bears N11°W 8 lks.; missing.
A 4' rock bluff bears South 4 lks.; now in place.

RESTORATION by A. Gibson, 1958

Reset original stone in mound of rock (found, in place) from which a:

32" Fir bears S82½°E 77.6 ft.; missing, point now in slide Area.
12" Fir stump bears S27½°W 9.7 ft.; now 12" stump in place, scribes
RS359 visible.
4" high rock bluff bears S5½°W 5.0 ft.; now 4' rock bluff in place,
scribes XBO (2" letters) 2' up from bottom.
4" x 4" x 48" WPCP bears NE 2.5 ft.; found out of place down hill.

REWITNESSED

From above stone in mound of stone, a:


17" Alder bears N65°E 25.4 ft. to bark scribes T22S R11W S3 BT.
10" Alder bears S06°E 29.5 ft. to bark scribes T22S R11W S10 BT RS359.

Reset 4" x 4" x 48" white painted Cedar post S15°E 5.3 ft. from cornerstone.
Oregon State Forestry Department metal location poster on 17" Alder BT. Also
poster on 10" Alder BT.

Dated June 8, 1976

REWITNESSED by Anthony J. Klosterman under my direction.
Anthony J. Klosterman, Engineer

Present and witnessed by James M. McIntosh



#142 ✓