

FILED

RECEIVED *27/*

JUL 1 1976

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

REWITNESSED CORNER FOR STATE OF OREGON--DEPARTMENT OF FORESTRY

Section corner common to Sections 11 and 15 (North end), T23S, R10W, W.M.,  
Douglas County, Oregon.

ORIGINAL

Post (missing) from which a:

- 24" Fir bears S90°E 85 lks.; now 63" stump in place, face burned away.
- 24" Fir bears S57°W 63 lks.; now 46" stump in place, scribes T and parts of backcast on burnt face exposed.

RESTORATION by A. Gibson, 1972

1½" x 36" G.I.P. (found in place) from which a:

- 13" Fir bears S26½°W 76.2 ft.; missing, in new cat road location.
- 56" Fir bears S84°E 40.1 ft.; now 56" stump, in place, scribes T23S R10W S11 BT visible.
- 4" x 4" x 72" WPCP bears S64°E 2.6 ft.; found, in place.

REWITNESSED

From above 1½" x 36" G.I.P. a:



- 57" Fir stump bears S87°W 15.8 ft. to face; scribed T23S R10W S15 BT RS359.
- 63" Fir stump (original) bears S90°E 55.0 ft. to face; scribed T23S R10W S11 BT.

Oregon State Forestry Department metal location poster on 4" x 4" x 72" WPCP S64°E 2.6 ft.

Dated June 14, 1976

Rewitnessed by Anthony J. Klosterman under my direction.  
Anthony J. Klosterman, Engineer

Present and witnessed by James M. McIntosh



#100