

UMPQUA SURVEYING COMPANY

P. O. Box 791
Myrtle Creek, Oregon 97457

626 N.E. Division Street
Telephone (503) 863-5201

MARCH 1982

SURVEY NARRATIVE TO ACCOMPANY PLAT OF
SECTION 34, TOWNSHIP 29 SOUTH, RANGE 1 EAST, WILLAMETTE MERRIDIAN,
FOR USDA FOREST SERVICE, UMPQUA NATIONAL FOREST

PURPOSE: TO SET CORNERS AND POST THE BOUNDARY BETWEEN U.S. FOREST SERVICE
LAND & LAND DESCRIBED IN DEED # 172990.

HISTORY: THE ORIGINAL SURVEY WAS CONDUCTED BY FRED MENSCH, 1910. THE G.L.O.
PLAT WAS APPROVED ON NOVEMBER 11, 1914.

THE SOUTH LINE OF THE TOWNSHIP WAS RESURVEYED IN 1937 BY NORMAN D.
PRICE. REFERENCE TO TOWNSHIP 30 SOUTH, WAS DELETED FROM THE CORNERS
OF TOWNSHIP 29 SOUTH ON THE TOWNSHIP LINE AT THAT TIME. THE GENERAL
LAND OFFICE PLAT OF OCTOBER 31, 1928 DELINEATES THE PRICE SURVEY.

EQUIPMENT: LEITZ T60D THEODOLITE, MACH II, BEETLE 1000S, AND 100 FT. TAPE.

CORNER ACCESSORIES: ALL BEARING TREES SCRIBED IN THE COURSE OF THIS SURVEY
HAVE A 3/4" BRASS WASHER STAMPED "LS866" NAILED TO THE
LOWER BLAZE.

MEASUREMENTS TO BEARING TREES TAKEN TO THE CENTER OF THE
ROOT CROWN.

THE FOLLOWING LETTERS REFER TO THE CORNERS ON THE ACCOMPANYING PLAT.

A. FOUND

18" HEMLOCK N86⁰E 10.1, SCAR

7" HEMLOCK S29⁰E 5.3, SCAR

B. FOUND

28" D-FIR, N68⁰30'E 15.2, SCAR


22" D-FIR, S83⁰15'E 6.6, SCAR

23" D-FIR, S50⁰45'W 15.2, SCAR

12" D-FIR, N50⁰W 14.1, SCAR

C.S. File 58 / 143 - 34A

Map File 91 / 43



PAGE 2 OF 3
NARRATIVE FOR PLAT OF SURVEY IN
SECTION 34, TOWNSHIP 29 SOUTH, RANGE 1 EAST,
WILLAMETTE MERRIDIAN

C. FOUND

18" PINE, N47°30'E 38.5, SCAR

18" D-FIR, S83°W 21.0, SCAR

D. SCRIBED

12" D-FIR, S82°45'E 72.7

23" D-FIR, N21°10'W 44.3

BOTH TREES SCRIBED "C¼ S34 BT"

E. FOUND

22" PINE, S25°30'E 37.2, SCAR

21" D-FIR, N52°45'W 41.5, SCAR

F. FOUND

15" MADRONE, S44°45'W 14.3, FACE DESTROYED

32" PINE, N28°30'E 64.2, SCAR

50" D-FIR, N44°W 13.2, SCAR

G. SCRIBED

10" D-FIR, N16°45'E 70.9

15" D-FIR, S9°30'W 15.2

BOTH TREES SCRIBED "NE NE 1/64 S34 BT"

H. SCRIBED

16" D-FIR, N39°30'W 44.7, "NN 1/64 S34 BT"

13" D-FIR, S81°E 17.8 "NN 1/54 S35 BT"

I. SCRIBED

17" D-FIR, N53°W 9.1


10" D-FIR, S51°30'E 12.4

BOTH TREES SCRIBED "CS SE NE 1/256 S34 BT"

J. SCRIBED

16" D-FIR, S27°20'E 15.0 "SSN 1/256 S35 BT"

8" D-FIR, S64°W 44.0 "SSN 1/256 S34 BT"



C.S. File 58, 143 - 34B

Map File 91, 43

PAGE 3 OF 3.
NARRATIVE FOR PLAT OF SURVEY IN
SECTION 34, TOWNSHIP 29 SOUTH, RANGE 1 EAST,
WILLAMETTE MERIDIAN

A 6" RED BAND, APPROXIMATELY 6" ABOVE UPPER BLAZE, WAS PAINTED AROUND EACH BEARING TREE. THE SCRIBED FACES WERE PAINTED RED. USFS BEARING TREE TAGS 54-3 WERE NAILED ABOVE UPPER BLAZES. USFS SIGNS 54-9 WERE NAILED TO BACK OF ALL TREES PERTAINING TO SET CORNERS. USFS SIGNS 54-4 WERE NAILED TO BACK OF TREES PERTAINING TO FOUND 1/4 AND SECTION CORNERS.



C.S File 58 / 143 - 34 C

Map File 91 / 43