

UMPQUA SURVEYING COMPANY

P. O. Box 791
Myrtle Creek, Oregon 97457

MARCH 1932

626 N.E. Division Street
Telephone (503) 863-5201

SURVEY NARRATIVE TO ACCOMPANY PLAT OF
SECTION 35, TOWNSHIP 29 SOUTH, RANGE 1 EAST, WILLAMETTE MERRIDIAN,
FOR USDA FOREST SERVICE, UMPQUA NATIONAL FOREST

PURPOSE: TO SET CORNERS AND POST THE BOUNDARY BETWEEN U.S. FOREST
LAND & LAND DESCRIBED IN DEED # 172990.

HISTORY: THE ORIGINAL SURVEY WAS CONDUCTED BY FRED MENSCH, 1910.
THE G.L.O. PLAT WAS APPROVED ON NOVEMBER 11, 1914.

THE SOUTH LINE OF THE TOWNSHIP WAS RESURVEYED IN 1937 BY NORMAN
D. PRICE. REFERENCE TO TOWNSHIP 30 SOUTH WAS DELETED FROM THE
CORNERS OF TOWNSHIP 29 SOUTH ON THE TOWNSHIP LINE AT THAT TIME.
THE GENERAL LAND OFFICE PLAT OF OCTOBER 31, 1938 DELINEATES THE
PRICE SURVEY.

EQUIPMENT: LEITZ T60D THEODOLITE, MACH II, BEETLE 1000S, AND 100 FT. TAPE.

CORNER ACCESSORIES: ALL BEARING TREES SCRIBED IN THE COURSE OF THIS SURVEY
HAVE A 3/4" BRASS WASHER STAMPED "LS866" NAILED TO THE
LOWER BLAZE.

MEASUREMENTS TO BEARING TREES TAKEN TO THE CENTER OF THE
ROOT CROWN.


THE FOLLOWING LETTERS REFER TO THE CORNERS ON THE ACCOMPANYING PLAT.

A. FOUND

28" D-FIR, N68⁰30'E 15.2, SCAR
22" D-FIR, S83⁰15'E 6.6, SCAR
23" D-FIR, S50⁰45'W 15.2, SCAR
12" D-FIR, N50⁰W 14.1, SCAR

B. FOUND

15" MADRONE, N12⁰45'W 12.2, SCRIBE PARTLY VISIBLE
19" D-FIR, S15⁰15'E 19.4, SCAR



C.S. File 58 / 143 -35A

Map File 91 / 44

PAGE 2 OF 3
NARRATIVE FOR PLAT OF SURVEY IN
SECTION 35, TOWNSHIP 29 SOUTH, RANGE 1 EAST,
WILLAMETTE MERRIDIAN

C. FOUND

22" PINE, S25°30'E 37.2, SCAR
21" D-FIR, N52°45'W 41.5 SCAR

D. SCRIBED

13" D-FIR, S39°40'W 23.8
10" D-FIR, N80°20'W 33.5
BOTH TREES SCRIBED "C¼ S35 BT"

E. FOUND

18" PINE, S47°30'W 38.8, SCRIBE PARTLY VISIBLE
28" D-FIR STUMP, N83°W 6.0, SCAR
31" D-FIR STUMP, N32°30'E 49.7 "BT" VISIBLE
18" D-FIR, S84°30'E 91.5, "¼ S36 CS BT"

F. FOUND

16" D-FIR, N37°45'W 37.1, SCAR
15" D-FIR, S80°15'E 13.5, SCAR
20" D-FIR, N55°30'E 21.4, SCAR

G. SCRIBED

16" D-FIR, N39°30'W 44.7 "NN 1/64 S34 BT"
13" D-FIR, S81°E 17.8 "NN 1/64 S35 BT"

H. SCRIBED

14" D-FIR, S78°E 32.0
13" D-FIR, N54°W 29.9
BOTH TREES SCRIBED "NW NW 1/64 S35 BT"

I. SCRIBED

16" OAK, S24°20'W 96.2
23" PINE, N38°30'E 127.5
BOTH TREES SCRIBED "C W NW 1/64 BT"



C.S File 58, 143 - 35B

Map File 21, 44