

RESTORATION OF 1/4 CORNER BETWEEN SECTION 21 AND SECTION 28, TOWNSHIP 30 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN.

I RESTORED THE 1/4 CORNER BETWEEN SECTION 21 AND SECTION 28 FROM THE FOLLOWING EVIDENCE.

1. I FOUND A FENCE CORNER POST WITH OLD BARB WIRE AT ITS' BASE. THE WIRE, NOW ON THE GROUND, IS STILL CONTINUOUSLY STRUNG. THE FENCE EVIDENCE EXTENDS WESTERLY AND SOUTHERLY FROM THE ABOVE CORNER IN NEARLY CARDINAL DIRECTIONS.

2. I FOUND THE REMAINS OF A DOUGLAS FIR TREE, AS IDENTIFIED BY BARK CHARACTERISTICS, IN A GROUND DEPRESSION ENCIRCLED BY BARK. THE REMAINS BEAR NORTH 80° WEST 13.2 FEET FROM THE FENCE CORNER. THE BARK RING HAS AN INSIDE DIAMETER OF APPROXIMATELY 18 INCHES.

3. I ALSO FOUND THE REMAINS OF A DOUGLAS FIR TREE, AS IDENTIFIED BY BARK CHARACTERISTICS, IN A GROUND DEPRESSION ENCIRCLED BY BARK. THE REMAINS BEAR SOUTH 54° WEST 13.2 FEET FROM THE FENCE CORNER. THE APPROXIMATE INSIDE DIAMETER OF THE BARK RING IS 18 INCHES.

4. BOTH OF THE ORIGINAL BEARING TREES ARE RECORDED AT THE ABOVE DISTANCES AND BEARINGS. BOTH OF THE ORIGINAL TREES WERE 15 INCHES IN DIAMETER. IT APPEARS AS THOUGH BOTH TREES DIED AFTER BEING SCRIBED.

5. I FIND THAT THE DISTANCE AND BEARING RELATIONSHIP BETWEEN OTHER ORIGINAL CORNERS AND THE FENCE CORNER IS WITHIN THE ACCURACY OF THE ORIGINAL SURVEY AS DETERMINED BY MY RETRACEMENT OF OTHER ORIGINAL LINES IN THIS AREA.

6. VERN LERWILL, A RANCHER IN THE TILLER AREA, TOLD ME THAT THIS FENCE CORNER IS COMMONLY BELIEVED TO BE THE SAID 1/4 CORNER. ALTHOUGH THE ABOVE IS HEARSAY EVIDENCE, IT AGREES WITH OTHER FINDINGS.

7. I MONUMENTED THE QUARTER CORNER WITH A 2" X 30" IRON PIPE WITH A BRASS CAP AND SCRIBED NEW BEARING TREES AS SHOWN ON THE CONCURRENTLY FILED PLAT.



C.S. File 58.....7.156-2A

Map File M65.166.....

M 65-66

RESTORATION OF 1/4 CORNER BETWEEN SECTION 21 AND SECTION 28, TOWNSHIP 30 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN.

I RESTORED THE 1/4 CORNER BETWEEN SECTION 21 AND SECTION 28 FROM THE FOLLOWING EVIDENCE.

1. I FOUND A FENCE CORNER POST WITH OLD BARB WIRE AT ITS' BASE. THE WIRE, NOW ON THE GROUND, IS STILL CONTINUOUSLY STRUNG. THE FENCE EVIDENCE EXTENDS WESTERLY AND SOUTHERLY FROM THE ABOVE CORNER IN NEARLY CARDINAL DIRECTIONS.

2. I FOUND THE REMAINS OF A DOUGLAS FIR TREE, AS IDENTIFIED BY BARK CHARACTERISTICS, IN A GROUND DEPRESSION ENCIRCLED BY BARK. THE REMAINS BEAR NORTH 80° WEST 13.2 FEET FROM THE FENCE CORNER. THE BARK RING HAS AN INSIDE DIAMETER OF APPROXIMATELY 18 INCHES.


3. I ALSO FOUND THE REMAINS OF A DOUGLAS FIR TREE, AS IDENTIFIED BY BARK CHARACTERISTICS, IN A GROUND DEPRESSION ENCIRCLED BY BARK. THE REMAINS BEAR SOUTH 54° WEST 13.2 FEET FROM THE FENCE CORNER. THE APPROXIMATE INSIDE DIAMETER OF THE BARK RING IS 18 INCHES.

4. BOTH OF THE ORIGINAL BEARING TREES ARE RECORDED AT THE ABOVE DISTANCES AND BEARINGS. BOTH OF THE ORIGINAL TREES WERE 15 INCHES IN DIAMETER. IT APPEARS AS THOUGH BOTH TREES DIED AFTER BEING SCRIBED.

5. I FIND THAT THE DISTANCE AND BEARING RELATIONSHIP BETWEEN OTHER ORIGINAL CORNERS AND THE FENCE CORNER IS WITHIN THE ACCURACY OF THE ORIGINAL SURVEY AS DETERMINED BY MY RETRACEMENT OF OTHER ORIGINAL LINES IN THIS AREA.

6. VERN LERWILL, A RANCHER IN THE TILLER AREA, TOLD ME THAT THIS FENCE CORNER IS COMMONLY BELIEVED TO BE THE SAID 1/4 CORNER. ALTHOUGH THE ABOVE IS HEARSAY EVIDENCE, IT AGREES WITH OTHER FINDINGS.

7. I MONUMENTED THE QUARTER CORNER WITH A 2" X 30" IRON PIPE WITH A BRASS CAP AND SCRIBED NEW BEARING TREES AS SHOWN ON THE CONCURRENTLY FILED PLAT.



C.S. File 58 7156-2b

Map File M65 166

#168