


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

As found by Fred Mensch, October 21, 1906: The closing corner of sections 1 and 2, T 32 S, R 2 W, which is a basalt stone 6 x 12 x 5 inches above the ground, firmly set. Marked and witnessed as described by the surveyor general.



Description of corner evidence found:

Found 2" iron pipe with 3" Brass Cap, 6" above ground. With Trees:

- a Douglas-fir stump, 12" diam. bears S 3° W, 18.5 feet, scribe visible.(badly rotted)
- a Douglas-fir stump, 10" diam. bears S 70½° E, 26.4 feet, scribe visible.(badly rotted)
- a Douglas-fir, 18" diam. bears S 27° W, 78.5 feet, good healed blaze.
- a Douglas-fir, 14" diam. bears S 79° E, 63.4 feet, good healed blaze.

Original corner stone set alongside 2" iron pipe.

Corner lies on West slope at the Northwest corner of logged unit.

Description of monument and accessories established to perpetuate the original location of this corner

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 14, 1961
GLENN S. BAUGHMAN
536

Office of Surveyor County of Douglas
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 6 day of July, 1978, at 8 o'clock a.m. (signed)
Francis L. Ingram by Gregory E. Mitchell
 (COUNTY OFFICIAL) (DEPUTY)