

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Fred Mensch October 1906. I re-established the corner in its original position as follows:


a white-oak, 12" diam. for corner of sections 25, 26, 35 and 36. I mkd T 31 S S 25 on NE, R 2 W S 36 on SE, S 35 on SW and S 26 on NW side, with 1 notch on S and E sides, from which

a fir, 30" diam. bears N 35° E 9 lks dist. mkd T 31 S R 2 W S 25 BT.

a cedar, 10" diam. bears S 60° E 21 lks dist. mkd T 31 S R 2 W S 36 BT.

a white-oak, 20" diam. bears S 30° W 8 lks dist. mkd T 31 S R 2 W S 35 BT.

a white-oak, 20" diam. bears N 45° W 23 lks dist. mkd T 31 S R 2 W S 26 BT.



Description of corner evidence found:

Corner lies on broad flat sloping slightly East. #67
Found 1" iron pipe with 2" Brass Cap 14" above ground. With trees:

a cedar, 22" diam. bears S 60° E., 13.9 feet, good blazed face.

a white-oak, 26" diam. bears S 30° W., 5.3 feet, good blazed face.

a Douglas-fir, 36" diam. bears N 35° E., 5.7 feet, (now down) good blazed face.

a white-oak snag, 20" diam. bears N 45° W., 15.2 feet, no face visible.

a Douglas-fir, 10" diam. bears N 29° W., 26.7 feet, good blazed face. (record N 52 W, 39.3 feet)

a Douglas-fir, 10" diam. bears N 62° E., 39.0 feet, good blazed face. (now down) (record N 29° E., 27.0 feet)

a white-fir, 8" diam. bears N 85° E., 35.9 feet,

Description of monument and accessories established to perpetuate the original location of this corner

I Scribed " T 31 S R 2 W S 25 BT" on double blazed face, of White-fir, 8" diam. bears N 85° E., 35.9 feet.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Glenn S. Baughman
OREGON
JULY 14, 1961
GLENN S. BAUGHMAN
536

Office of _____ Surveyor _____ County of _____ Douglas _____
Oregon
State of _____, I hereby certify that the within instrument was filed in this office
for record on the 6 day of July, 1978, at 8 o'clock a.m., (signed)
Francis L. Ingram by *Gregory E. Smith*
(COUNTY OFFICIAL) (DEPUTY)

#189 X