


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: 1917 retracement survey by Elmer Strickler. Renewed by John Powell 1968 Set stone for corner (original). Replaced with brass cap on 1" iron pipe.




Original trees marked:
 30" Fir N. 45° 30' E. 19 links
 15" Fir N. 47° W. 58 links

Renewed trees:
 24" Douglas Fir N. 38.0 feet
 20" Douglas Fir N. 10° W. 25.7 feet
 8" White Fir S. 24° W. 18.6 feet

Description of corner evidence found:

Found 1" iron pipe with brass cap.
 10" White Fir S. 24° W. 18.6 feet
 20" Douglas Fir N. 10° W. 25.7 feet
 24" Douglas Fir (Snag) N. 38.0 feet
 30" Douglas Fir (Down) N. 45 1/2° E. 12.5 feet

County Surveyor
Office



T. 30 S. R. 2 W.
1968

Description of monument and accessories I established to perpetuate the original location of this corner

I marked 6" White Fir N. 24° E. 31.1 feet scribed "T. 29 S., R 2 W. 536 BT" on a double blaze and attached brass washer stamped Land Surveyor 536 on lower face.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Glenn S. Baughman

OREGON
JULY 14, 1961
GLENN S. BAUGHMAN
536

FILED
RECEIVED

MAY 28 1979

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE

Office of County Surveyor County of Douglas
 Oregon
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 22 day of May, 1979, at 9 o'clock a.m., (signed)
 Francis L. Ingram by *Virginia A. Langford*
 (COUNTY OFFICIAL) (DEPUTY)

Duplicate
#111 T29-2
#119 T30-2