


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by W.H. Byars, Deputy Surveyor, under Contract No. 152, who set a post from which:

- A laurel, 12 ins. diam., bears N 45° E, 8 lks dist.
- A laurel, 16 ins. diam., bears S 10° E, 32 lks dist.
- A fir, 6 ins. diam., bears N 50° W, 34 lks dist.
- A laurel, 10 ins. diam., bears N 50° W, 34 lks dist.



The corner was renewed in 1894 by William M. Bushey, Deputy Surveyor under Contract No. 620, who set a new post and marked new bearing trees:

- A sugar pine, 10 ins. diam., bears N 15° E, 93½ lks dist.
- A laurel, 16 ins. diam., bears N 49° W, 78½ lks dist.

The corner was renewed by Geo. J. Wenderoth, Deputy Douglas County Surveyor, in 1946, who set a 1" iron pipe at corner point and marked a new bearing tree:

- A 20 in. madrone, bears S 24° 30' E, 39.0 ft.

The corner was renewed by John M. Powell, Douglas County Surveyors Office in 1966, who set a 1" ~~iron pipe~~ iron pipe with brass cap marked: "County Surveyor's Office, T31S R3W S27 S28 S33 S34 1966" and marked a new bearing tree:

- A 5 in. hemlock, bears N 5° W, 17.9 ft.

DESCRIPTION OF CORNER EVIDENCE FOUND: A 1" iron pipe, firmly set, projecting 12" above the ground with a 2½" brass cap marked: "County Surveyor's Office, T31S R3W S27 S28 S33 S34 1966", from which the original bearing trees:

- A 26 in. laurel, with center rotted out, bears S 6° E, 21.1 ft. to face (Record S 10° E)
- A 15 in. fir, with healed blaze, bears S 39° W, 17.2 ft. to face (Record S 35° W)

and bearing trees marked by Bushey:

- A 35 in. rotted sugar pine stump, with healed blaze, bears N 15° E, 63.4 ft. (Record 61.7')
- A 22 in. laurel stump, with scribe marks "R 3 S 28" vis. bears N 49° W, 51.8 ft.

and bearing trees marked by Wenderoth:

- A 22 in. laurel, with scribe marks "S 34 BT" vis. bears S 24½° E, 39.0 ft.

Description of monument and accessories established to perpetuate the original location of this corner

Marked new bearing trees:

- A 12 in. douglas fir, bears N 42° E, 122.1 ft., marked: "T31S R3W S27 BT" on a double blaze and nailed a brass washer, stamped "LS 536" into lower blaze.
- A 8 in. douglas fir, bears N 8° W, 68.7 ft., marked: "T31S R3W S28 BT" on a double blaze and nailed a brass washer, stamped "LS 536" into lower blaze.

Compass declination 20° East.

REGISTERED PROFESSIONAL LAND SURVEYOR

Glenn S. Baughman

OREGON
JULY 14, 1961
GLENN S. BAUGHMAN
536

Office of County Surveyor County of Douglas
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 2 day of October, 1979, at 3 o'clock P. m., (signed)
Francis L. Ingram by Virginia A. Hager
 (COUNTY OFFICIAL) (DEPUTY)

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

88

#207 x e