


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The North 1/4 corner of Section 5, T32S, R1W was originally set via single proportion measurement by Professional Land Surveyor Leland P. Lovejoy in 1953.




Description of corner evidence found:

Found the 3/4" C.I.P. as set by Lovejoy, from which:
 A W. Fir 8" dia. bears S39°03'W 18.0 ft. (Rec. S 38°W 16.6ft.)
 A G. Fir 8" dia. bears S 31°00'E 19.0 ft. (Rec. W. Fir S 28°E 19.4 ft.)

A 2" G.I.P. with a 2 1/2" B.C. at the Section corner
 S 32 & S 33, T. 31 S., R. 1 W. bears S 89°52'48" E 158.37.

Description of monument and accessories established to perpetuate the original location of this corner:

I set a 2" x 30" C.I.P. with a 2 1/2" brass cap over found pipe, exposed 16" in a mound of stone and marked:



variation = 19°44'.

FILED
 RECEIVED
 FEB 8 1980
 COUNTY SURVEYOR
 DOUGLAS COUNTY, ORE

T31-1 #51-
 T32-1 #19-6

Office of... Surveyor..... County of... Douglas
 State of... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 8th day of... February....., 1980.

...Francis L. Ingram..... by *Kurt Weaver*
 (COUNTY OFFICIAL) (DEPUTY)

Witness my hand and seal this 8th day of February, 1980

Form R6-7100-57 (9/71)

Jolly Rakulak
 Notary Public for Oregon
 My commission expires 3-27-81

GPO 799-509

#82 T32-1 X
 #184 T31-1 X

G.S. File No. 58/176-3A 58/176

8