


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established in 1883 by Rufus Moore under General Land Office Contract No. 475 who set a Fir post, from which:

- a 6" Fir bears N75°E, 10 Lks.
- a 10" Fir bears S34°W, 4 Lks.



The corner was renewed in 1968 by the Douglas County Surveyors Office who set a Brass Cap, from which:

- a 14" Hemlock bears S45°E, 26.8 feet, marked "1/4 S16 CS BT"
- a 12" D. Fir bears N89°E, 65.1 feet, marked "1/4 S17 CS BT"

The corner was renewed in 1974 by the Douglas County Surveyors Office who reset the Brass Cap.

Description of corner evidence found:

Found a 1" iron pipe, projecting 4" above the ground, with a 2-1/2" Brass Cap marked:

"T32S R1W 1/4 S17 S16 1968"

From which:

- a 22" Fir stob, original BT, bears S34°W, 2.6 feet
- a 14" Hemlock with scribe marks "1/4 S17 CS BT" visible on a partially healed blaze bears S45°W, 26.8 feet.
- a 14" D. Fir stump with scribe marks "1/4 S16 CS BT" visible on a partially healed blaze bears N89°E, 65.1 feet.

Description of monument and accessories I established to perpetuate the original location of this corner

New bearing tree:

an 8" D. Fir bears S77°E, 52.1 feet, I marked "1/4 S17 BT" on a double blaze and nailed a Brass Washer stamped "LS 536" into lower blaze.



Office of SURVEYOR County of DOUGLAS
 State of OREGON, I hereby certify that the within instrument was filed in this office
 for record on the 18 day of JULY, 1979, at 2 o'clock 30 m. (signed)
Glenn S. Baughman by Robert W. Brady
 (COUNTY OFFICIAL) (DEPUTY)

79 X