

M 84-46

MINOR LAND PARTITION SURVEY for LYNN STONE in the Southwest $\frac{1}{4}$, Section 8, Township 30 South, Range 5 West, Willamette Meridian, Douglas County, Oregon. Lot 14, March Plat " A ".

Survey began with the location of all of the original lot corners of said Lot 14. I used the most Northerly lot line as my " Base of Bearing ".

I go to the most Northwesterly corner of Lot 14, and run South $89^{\circ} 23' 00''$ East 359.33 feet to the most Northeasterly corner of said Lot.

Thence I run South $1^{\circ} 22' 53''$ West and set or find the following corners.

At 60.00 feet I set a $\frac{5}{8}$ inch iron rod.

At 261.40 feet or 201.40 feet further I find the most Southeasterly corner of said Lot 14.

I now go to the said Southeast corner and run North $89^{\circ} 28' 50''$ West and set or find the following corners.

At 215.15 feet where I set a $\frac{5}{8}$ inch iron rod.

At 332.15 feet or 117.00 feet further, I find the most Southwesterly corner of said Lot 14.

I now go to the said Southwesterly corner Lot 14 and run North $0^{\circ} 53' 10''$ East 236.82 feet where I find a interior corner to Lot 14.

I then run South $46^{\circ} 10' 40''$ East 137.18 feet from said interior corner and set a $\frac{5}{8}$ inch iron rod.

I now run from just said set $\frac{5}{8}$ inch iron rod North $51^{\circ} 55' 20''$ East and set the following rods.

At 25.25 feet.

At 64.64 feet or 39.39 feet further.

FILED


RECEIVED ^S _{HH}

JUL 22 1980

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

DATE OF SURVEY: July 2, 1980
SURVEYOR: John H. Markham Jr.
Myrtle Creek, OR.
ph. 503-863-4590

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
SEPTEMBER 23, 1977
JOHN H. MARKHAM, JR.
1261

C.S. File 58 / 220-16

Map File M 84-46