

M 87-67

MAJOR LAND PARTITION SURVEY for Denzil and Cheryl Whitney in the Northeast $\frac{1}{4}$, Section 19, Township 30 South, Range 5 West, Willamette Meridian, Douglas County, Oregon.

Survey began with the location of monuments set by M 87-22, C.S. 58/200, and the North quarter and East sixteenth corner to Section 19, Set by B.L.M.. From the above mentioned survey (M 87-22), I find the 5/8 inch iron rod and the 1/2 inch iron rod that defines the North line of D.L.C. 43 (YOKUM). This line is used as my " Base of Bearing ".

I now set at the said 5/8 inch iron rod and run S 89° 09' 02" W and find or set the following corners.

At 375.00 feet, I set a 3/4 inch iron pipe.

At 401.87 feet or 26.87 feet further, I find a 1/2 inch iron rod.

At 912.83 feet or 510.96 feet further, I set a 3/4 inch iron pipe on the high bank of the south side of the South Umpqua River. Note: Corner of a existing fence bears North 11.40 feet.


I now return to the said 5/8 inch iron rod and run N 4° 40' 30" W 80.01 feet to a 5/8 inch iron rod. (shown in C.S.58/200, set by O.S.R.W..

Thence I run N 3° 24' 50" W 204.20 feet and find a 1 inch iron pipe on the high bank of the south side of the South Umpqua River.

I now go to the first said set 3/4 inch iron pipe and first run N 0° 50' 52" W 224.03 feet and set a 3/4 inch iron pipe on the said high bank.

I then return to the said set 3/4 inch iron pipe and run N 30° 32' 05" W 1439.45 feet and find the North quarter corner to Section 19, Township 30 South, Range 5 West. I used this line as my tie.

DATE OF SURVEY: May 23, 1981
SURVEYOR: John H. Markham Jr.
Myrtle Creek, OR
ph. 503-863-4590



FILED *BS*

RECEIVED *HJ*

JUN 8 1981

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.