

NARRATIVE OF SURVEY  
See Map in County Surveyor's File MAP FILE M 92-33

SECTION LINE and PROPERTY SURVEY for William B. Strobridge, located in the Southwest  $\frac{1}{4}$  and the Southeast  $\frac{1}{4}$  of Section 19, Township 30 South, Range 5 West, Willamette Meridian, Douglas County, Oregon.

Survey began with locating the two southern section corners to Section 19 ( both being Brass Caps ).

I then ran a random line between the two said section corners, and returned on the true line. Starting at the Southeast corner of said section, I found or set the following monuments along said section line.

At 1398.31 feet, I set a  $1\frac{1}{4}$  inch by 36 inch galv. pipe with Brass Cap mkd. L.S. 1261 Bearing Trees-

E  $1/16$  S 19  
S 30  
1982

A 12" W.Oak bears N  $64^{\circ}$  W 8.6 feet.  
A 8" W.Oak bears S  $52^{\circ}$  E 16.8 feet.

At 2725.56 feet or 1327.25 feet further, I set a  $5/8$  inch by 30 inch iron rod with Al. cap mkd. L.S. 1261, this point is where the section line and a old fence line cross.

At 2796.63 feet or 71.07 feet further, I set a  $1\frac{1}{4}$  inch by 36 inch galv. pipe with Brass Cap mkd. L.S. 1261 Bearing Trees-

$1/4$  S 19  
S 30  
1982

A 18" Maple bears S  $22^{\circ}$  E 4.0 feet  
A 24" Fir bears N  $25^{\circ}$  E 38.3 feet

this corner was set by proportionate method. No sign of the original  $\frac{1}{4}$  corner.

At 3006.40 feet or 209.77 feet further, I set a  $5/8$  inch by 30 inch iron rod with Al. cap mkd. L.S. 1261, this point marks high water mark of Cow Creek.

At 5747.07 feet or 2740.67 feet further, I find a Brass Cap that marks the Southwest section corner. Original survey shows this section line to bear North  $89^{\circ} 33' 00''$  East and was used as " Base of Bearing ".

I now return to the said set  $\frac{1}{4}$  corner and run on the true center of section line North  $0^{\circ} 31' 20''$  East, where I find or set the following monuments.

At 819.16 feet, I set a  $5/8$ " by 30" iron rod with Al. cap mkd. L.S. 1261, this point marks the southern side of County Road No. 20-A.

At 970.05 feet or 150.89 feet further, I set a  $5/8$ " by 30" iron rod with Al. cap mkd. L.S. 1261, this point marks the Northern side of said County Road.

At 5243.77 feet or 4273.72 feet further, I find the Brass Cap that marks the  $\frac{1}{4}$  corner common to Section 18 and 19.

I, now return to the said set  $5/8$ " iron rod that marks the southern side of said road and run along the right of way easterly North  $56^{\circ} 27' 20''$  East 68.17 feet to a  $3/4$  inch iron rod; thence North  $29^{\circ} 53' 28''$  West 20.00 feet to a  $3/4$  inch iron rod; thence North  $64^{\circ} 13' 12''$  East 73.56 feet, where I set a  $5/8$  inch by 30 inch iron rod with Al. cap mkd. L.S. 1261.

I then return to the said set  $5/8$ " iron rod that marks the northern side of said road and run North  $16^{\circ} 27' 23''$  East 118.49 feet to a  $5/8$  inch iron rod; thence North  $3^{\circ} 37' 48''$  East 230.29 feet to a  $5/8$  inch iron rod; thence North  $89^{\circ} 57' 42''$  East 89.70 feet to a  $5/8$  inch iron rod; ( note: a  $3/4$  inch iron pipe bears N  $0^{\circ} 10' 54''$  E 36.97 feet from this point), thence South  $2^{\circ} 33' 00''$  West 252.00 feet to a  $5/8$  inch iron rod.

DATE OF SURVEY: May 24, 1982

SURVEYOR: John H. Markham Jr.



Myrtle Creek, OR 97457  
ph. 503-863-4590

FILED *BS*

RECEIVED *BS*

JUL 13 1982

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.



C.S. File No. C.S. 58/220<sup>22</sup> (N)