

M 96-20

FILED
RECEIVED *BP*

OREGON CORNER RESTORATION FORM

MAR 22 1984

Section 25 Township 20S Range 94

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

County Douglas Date 3-13-84

Corner Designation

S.W. Corner	27	25
Section 25	34	35

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. Thomas V. Tillman and Joseph S. Gawron F.L.O. Survey in 1953 - 1954. Jelley and Bill Glenn Survey in 1953

Monument(s) & Accessories Found: (Condition and Source)

Found 1953 F.L.O. Brass Cap set firmly in ground. Found steel fence post set by Jelley and Glenn in 1967 beside Brass Cap. wired survey attention sign to steel fence post.

18" Fir, S11W, 57.4' (Scar Vis.), 1953 BT. Record S11 1/4 W, 57.4'

25" Fir, N45W, 50.2' (Scar Vis.), 1953 BT. Record N45 1/4 W, 50.2'

25" Fir, S84E, 25.2' (Scar Vis.), 1953 BT. Record S833/4E, 25.1'

30" Fir, N83E, 27.6' (Scar Vis.), 1953 BT. Record N83 3/4 E, 28.4'

Monument Detail

Sketch

25" FIR
(SCAR VIS.)

FD. 1953 G.L.O.
BRASS CAP

N45°W
50.2'

N83°E
27.6'
S84°E
25.2'

30" FIR
(SCAR VIS.)

25" FIR
(SCAR VIS.)

S11°W
57.4'

18" FIR
(SCAR VIS.)

Monument Set (Procedures and Description)


New Accessories

None

Location & Comments

Corner lies on South- Compass Declination 20 1/2'
West slope about 300' Firm/Agency Roberts
Northeasterly of Surveying, Inc.
Smith river road. Address 29 west 29th St.
Corner lies in 100- Eugene, Oregon 97405
120 year old green Party Chief Les Roberts
timber. Notes Ted Baker
Witness Stu Duce

Surveyor's Seal



OK Lem

C.S. File No. 58/220 ^{23A} (w)