

Survey Number M 82-68

Survey Narrative To Comply With O.R.S. 209.250

Location: Section 20, T.32S., R.3W., W.M.

Survey for: U.S. Forest Service, Umpqua National Forest  
Roseburg, Oregon. Tiller Land Survey No. 39  
Contract No. 53-04H1-9-765N

Survey by: CHICKERING/GREEN EMPIRE, INC.  
360 S.E. "H" Street Suite B  
Grants Pass, Oregon 97526  
(Malcolm N. Clark, R.L.S. 601)

Date: December 1979 to April 1980

Equipment: Wild T-16 theodolite and K. & E. Auto Ranger


Purpose: To survey the boundaries of certain U.S. Forest Service lands in Section 20, to mark and post the boundary lines of certain U.S. Forest Service lands, to establish and monument certain corners of U.S. Forest lands, and to establish and monument the North one-quarter corner of Section 20.

Procedure: A solar observation was taken near the Southeast corner of Section 20 and was used as a bearing base for this survey. A closed traverse was run around the exterior boundary, measuring all angles by repetition, a minimum of two observations, and measuring all distances with an E.D.M., both in feet and meters. All existing controlling corners were tied by this traverse. All missing controlling corners were proportioned using Fred Mensch's plat dated October 15, 1914, as the basis of the proportions. The property line shown on the survey map were then run and closed onto the exterior boundary traverse. The property lines shown on the map are marked by 6 foot orange fiberglass fence posts and Forest Service boundary signs. All corner monuments set in this survey are 2 1/2 inch aluminum caps on a 2 inch (I.D.) by 30 inch flared aluminum pipe, set approximately 24 inches in the ground.

FILED  
RECEIVED JHM

APR 1 1980

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.



G. E. Ellis No. CS 58/227-1