

Survey Number M 83-54

Survey Narrative To Comply With O.R.S. 209.250

Location: Section 2, T.32S., R.3W., W.M.

Survey for: U.S. Forest Service, Umpqua National Forest
Roseburg, Oregon. Tiller Land Survey No. 39
Contract No. 53-04H1-97652N


Survey by: CHICKERING/GREEN EMPIRE, INC.
360 S.E. "H" Street Suite B
Grants Pass, Oregon 97526
(Malcolm N. Clark, R.L.S. 601)

Date: December 1979 to April 1980

Equipment: Wild T-16 theodolite and K. & E. AutoRanger

Purpose: To survey the boundaries of certain U.S. Forest Service lands in Section 2, to mark and post the boundary lines of certain U.S. Forest Service lands, to establish and monument certain corners of U.S. Forest Service lands, and to perpetuate the South one-quarter corner of Section 2.

Procedure: A solar observation was taken near the West one-quarter corner of Section 2, and was used as a bearing base for this survey. A closed traverse was run around the exterior boundary, measuring all angles by repetition, a minimum of two observations, and measuring all distances with an E.D.M., both in feet and meters. All existing controlling corners were tied by this traverse. The property lines shown on the survey map were then run and closed onto the exterior boundary traverse. The property lines shown on the map are marked by 6 foot orange fiberglass fence posts and Forest Service boundary signs. All corner monuments set in this survey are 2 1/2 inch aluminum caps on a 2 inch (I.D.) by 30 inch flared aluminum pipe, set approximately 24 inches in the ground.



58/227
58/100
G. S. File No: 58/100

M83-54

DOUGLAS COUNTY, OREGON

Memorandum for Mr. Malcolm Clark - Chickering/Green Empire June 30, 1980, 19

From Virginia Laugen - Records Supervisor
Douglas County Surveyors Office
Room 205 Justice Bldg.
Roseburg, OR 97470

Re: Survey for U. S. Forest Service, Section 2, T. 32 S., R. 3 W. W.M.

On the Tiller Land Survey No. 39, it was noted that the corner for Secs. 2, 1, 11 and 12 had a bearing tree with the wrong bearing drafted. It is the 18" White fir showing N.12°40'E; but to agree with the other survey filed, should be S.03°35'E.

You were contacted by telephone April 28 and we offered to make that correction for you if you would send us a letter so designating us to do so.

A prompt reply from you would clear this matter.

Thanks,

Virginia

Please make the necessary corrections. The telephone message was not passed onto me. I'm sorry for the delay.

Malcolm N. Clark

Malcolm N. Clark

FILED
RECEIVED
JUL 7 1980
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

G. & E. File No. 58/227-26