


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by Carl S. Nicklin, U. S. Deputy Surveyor, under Contract No. 664 in 1896, who set a 12" X 10" X 10" basalt stone 8" in the ground and marked "1/4" on the West face, from which:

A fir, 12 ins. diam., bears N. 26° E., 33 lks. dist.  
Marked 1/4 S BT.

A fir, 12 ins. diam., bears N. 55° W., 19 lks. dist.  
Marked 1/4 S BT.



Description of corner evidence found:


A 30" Douglas fir stump, original BT. I opened to find scribe marks "BT", bears N. 55° W. 12.5 feet.

A 26" Douglas fir, original BT. I opened to find scribe marks "4S", bears S. 26° E. 21.8 feet (Record N. 26° E.)

FILED  
 RECEIVED *JR*  
 OCT 2 1980  
 COUNTY SURVEYOR  
 DOUGLAS COUNTY, ORE

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" X 30" iron pipe, 24" in the ground in a 3 ft. diameter mound of stone with a 3" brass cap marked:



New bearing trees:

A 11" Douglas fir, bears N. 38° E., 33.6 feet marked: "1/4 S31 BT" on a double blaze with a brass washer stamped "LS 536" nailed into lower blaze.

A 13" Douglas fir, bears N. 11° W., 59.9 feet, marked: "1/4 S36 BT" on a double blaze with a brass washer stamped "LS 536" nailed into lower blaze.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

OREGON  
 JULY 14, 1957  
 GLENN S. BAUGHMAN  
 536

Office of.....Surveyor..... County of.. Douglas.....  
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the....2.... day of.....October....., 1980.

Francis L. Ingram..... by *Virginia A. Leugen*  
 (COUNTY OFFICIAL) (DEPUTY)

#133 T 24 W A  
 #6 T 24-18 X