

Shaner Engineering, Inc.

PLANNING • SURVEYING • ENGINEERING
P. O. BOX 1430
ROSEBURG, OREGON 97470

FILED
RECEIVED
133 S. E. MAIN
NOV 16 1982

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE
November 5, 1982

DESCRIPTION OF SECTION CORNER COMMON TO SECTIONS 14, 15, 22 & 23, T26S, R6W, W.M., DOUGLAS COUNTY, OREGON AS FOUND DURING MINOR LAND PARTITION SURVEY FOR K. MEAD

At the Section Corner common to Sections 14, 15, 22 & 23, T26S, R6W, W.M., Douglas County, Oregon, I found a 1" iron pipe with a 2 1/2" brass cap marked "COUNTY SURVEYOR'S OFFICE, 1959, S14, S15, S22, S23, T26S, R6W", from which a:

Original Bearing Trees

52" Oak BT snag, scribe "S" visible, bears N25 1/2°W, 207.4 feet to face. (Original G.L.O. record N27°W, 205.9 feet).

32" Oak BT snag with face scars, bears N68°E, 46.2 feet to face.

22" Oak BT, with healed over face, bears S76 3/4°E, 39.1 feet. (Original G.L.O. record 39.6 feet)

Bearing Trees marked by County Surveyor in 1959

24" Oak BT, with healed over face, bears S69°W, 23.7 feet. (Record S72°W, 24.3 feet)


16" Oak BT, with healed over face, bears N61°E, 17.8 feet.

14" Oak BT, with healed over face, bears N83°W, 44.2 feet. (Record N82°W, 45.2 feet)


Bruce A. Shaner,
Professional Land Surveyor

Mark Ramp, Instrument man

Lanse Wessel, Chainman



BA Shaner



184
+

C